GENERAL LI III




stered at the Post Office of New York, N. Y., as Second Class Matter. Copyright, 1994, by Munn & Co

Vol. XC.-1

NEW YORK, MARCH 5, 1904.

S CENTS A COPY



Corright 1994 by Moon & Co.

S. P. Langley

After a painting by Robert Gordon Bardio.

SCIENTIFIC AMERICAN

ESTABLISHED 1845

MUNN & CO. . .

Editors and Proprietors

Published Weekly at

No. 361 Broadway, New York

noney order, or by bank draft or check. MUNN & CO., MI Broadway, New York.

YORK, SATURDAY, MARCH 5, 1904.

The Editor is always glad to receive for examination illustrated articles on subjects or timely interest. If the photographs are charp, the articles short, and the facts authentic, the contributions will receive special attention. Accepted articles will be paid for at regular space rates.

THE HIGH-SPEED MOTOR-BOAT MODEL.

The growing pepularity of the high-speed motor boat is shown by the fact that an exhibition devoted entimely to small power-driven vessels of high speed has recently been held in this city in which an excellent exhibit was made of some of the latest and fastest of these craft and of the most approved types of engine used for their propulsion. The cause of the extremely high speed that is developed by these boats is two-fold. In the first place, it is due to the introduction and refinement of a new principle of modeling develop during the past few years, which is an entire departure in some respects from the accepted speed lines for fast vessels which have governed designers ever since the modeling of high-speed craft was placed upon a scientific basis. The other cause is to be found in the remarkable development of the gas engine, re-sulting in the production of a given horse power for a minimum amount of dead weight. It is the simultaneous production of a high-speed model and an ideal motor to drive it that is responsible for the wide spread interest in this fascinating form of sport.

The credit for the development of what might be called, for want of a more descriptive term, the motor-boat model, is shared equally by the yacht designers of the old and the new world; and we say this without any disparagement of the work done by the torpedo-boat builders, such as Thornycroft Yarrow in England, Normand in France, and Schichau Mention should be made of the speedy craft built by Herreshoff and Mosher in this country. work done by Kretschmer, naval constructor of the German navy. It is difficult to say just who was the originator of the type, and it is probable that it was an evolution that was the outcome of continued experiment and trial. Kretschmer, working on independent lines in Germany, seems to have clear title to originality in his own country, where he was en-abled to patent his "tetrahedral construction;" but we understand that his application in this country was denied on the ground that the same principle has been in use for some years in the Mosher boats. this connection we may mention that in the current issue of the SUPPLEMENT we publish the plans of one or two fast German launches of this design, together with a description of the principles upon which their were drawn.

The main object aimed at in the lines of this craft is to keep down wave-making, which at high speed is the chief cause of resistance. The water lines are practically straight from the bow almost to the stern, and the bow angle at the water line is twice as sharp as that of a boat of equal length and beam modeled on the old speed-line theories. Straight water lines are secured by placing the point of greatest beam at the extreme or almost extreme stern of the vessel, an arrangement which causes the immersed sections to vary from a sharp, deep V at the bow to a broad, shallow U at the stern. The sharp angles of the water line and the gradual change from V to U sections may be regarded as the cause of the inappreciable wave for mation, since the currents of displaced water are not subjected to a constant change in direction as in ordinary boats; and when these craft are driven at full d, only a slight bow-wave is formed and a rela tively small stern-wave, while no hollowing of the water at the sides of the boat is perceptible. Another advantage is that in spite of the great sharpness of the lines, the boat has a greater beam than one of equal fineness of line built upon the ordinary model, with a corresponding gain in stability. At the same time, these vessels are extremely sensitive to any disar-rangement of their trim, and if the proper trim be not whether principles that have been so successful in

small boats are capable of application to large ocean-going ships is, we think, open to question. This very

matter of trimming would, at the outset, present considerable difficulties of a commercial and operative quality. Mr. Kretschmer, however, has been engaged in designing upon his "tetrahedral" principles an ocean-going vessel of the size of "Kaiser Wilhelm II.," and on a length of 690 feet, a beam of 781/2 feet and a maximum draft forward of 241/2 feet, diminishing toward the stern, he produces a ship which, with an indicated horse power of 20,000, he expects to realize a speed of 24 knots. In this connection it is interesting to note that towing tank experiments carried out by the Russian navy department at St. Petersburg have demonstrated the merits of this form for the attain ment of high speed. For low speeds of 12 knots and under, no perceptible advantage is noticeable between the tetrahedral and the ordinary model; from 12 to 14 and even up to 16 knots, the towing tests showed that the tetrahedral form is at a disadvantage, since by reason of the greater amount of frictional surface preented, greater power is required for a given sp than with a ship constructed in accordance with the usual principles; but for speeds above those mentioned,

RAISING CARRIER PIGEONS

where wave-making is set up, the new design gains in

speed at a multiplying rate

The popularity of the homing, or carrier, pigeon has been greatly enhanced in the last few years by the annual races held in different parts of the country. the present time fanciers are arranging for a race during the coming summer, which will eclipse any thing heretofore attempted. The race will be for 500 miles, from Spartanburg, N. C., to Philadelphia, and over 2,000 birds are expected to enter the contest. be held on the Fourth of July, and in all prob ability most of the pigeons will cover the distance in The present record for the flight is 1,603 ten hours. vards in a minute, which in a 500-mile race should enable birds of ordinary speed to finish within ten or twelve hours.

The event will be one of a series of contests which have been held in the past ten years; but it will be the first 500-mile one in which anything like so many birds have started. In the 200-mile race of several years ago from Orangeburg, Va., 1,500 birds were liberated. In 1896 a smaller number of birds were started in the race. In this race two birds flew 614 miles in one day, and several have covered 600 miles in a day with apparent ease. The pigeons are carried to the starting place in baskets arranged especially The pigeons are carried for them, and liberated directly from the baskets if the day is favorable for an immediate start. Pigeon sheds are made to accommodate the birds for a pro longed stay in the event of unfavorable weather. The birds are shipped to the scene of the race by special cars under the direct care of the Pigeon-Flyers' Protective Association. Hundreds of birds have been lost in the past races through theft, and many owners of fine homing-pigeons have consequently been reluctant to enter their birds in the contests for fear of losing ent race a uniform style of lock In the pre for the baskets will be adopted, and only the care-takers will be provided with keys. If the locks are opened or picked, and pigeons stolen, the association will investigate and prosecute the offenders

There is no more delightful sport than pigeon racing of this character, nor any more enthusiastic sports-men than the breeders of the homing pigeons. Clubs devoted to raising and improving the ca tered in every State in the Union, and their memberships are all large; but there are tens of thousands of individual breeders who do not belong to any as-Thousands of these breeders enter home-raised pigeons in the races and sometimes win prizes which the professionals fail to capture

The best carrier pigeons are worth several hundred dollars in the market, and some cannot be purcha at any price. During the annual pigeon show at Madison Square Garden last year, \$200 and even \$300 were refused by the owners for some of their choicest pets The average exhibited were valued at \$25 and \$50. Prices, however, do not stand in the way of the pigeon fancier to-day, for excellent homing pigeons can be purchased for \$5 and less. One can start a loft with half a dozen breeders, and within a few seasons have all the birds desired. The loft is a simple affair where only a few birds are raised. The breeding quarters are separated from the living quarters, and a place large enough for the birds to stretch their wings is provided. The wonderful instinct of the homers is made apparent at an early age; but it is something that is partly due to training and development. A carrier pigeon that has never been released from its loft until full grown cannot find its way back over a long route. The process of training is necessary when pigeons take their first flight.

"Home," to the carrier pigeon, is where it was b There is no other home, although they have been trained to adopt a second home in some instances. When born in the loft, it is an easy matter for the eder to teach the pigeon to return to it. The pro-

cess of training consists simply in releasing the bird when first able to fly a short distance from the loft The pigeon will jump into the air, and after a few circles, fly straight to the loft. In the second flight the distance is increased, and so on until the bird's education is complete. This education must be conducted by the breeder with gentleness and due con sideration for the bird's feeling. If the distance for the first flight is too great for the pigeon, it will get confused, and it is liable to prove less accurate in its future flights. Each progressive step must be made the purpose of establishing the bird's distance and direction, and not to see how far it can be removed from the loft without losing the way in returning. A lost homing-pigeon is never quite the san n after being rescued and taken home. bird gains full maturity and its education has been completed by the process described, it seems capable of finding its way home from almost anywhere ased in Jacksonville have flown a thousand miles north to their homes without being lost.

When released, a homing-pigeon does not fly con tinuously unless the distance is short enough to enable it to reach home without stopping for rest. tance can be covered in ten or twelve hours, the pigeons apparently take little rest, but fly almost continuously until they reach their loft. In the few 1,000-mile races conducted years ago on the Atlantic sea coast from Florida to New York and Philadelphia, a number of the birds were lost, while others stopped on the way several times to rest; but the choicest birds which finished the long course were apparently on the wing most of the time, stopping possibly a few hours on the way to get food and rest. These long flights are not encouraged to any great extent any more, for the birds are not only frequently lost, but they cannot always get proper food along the route to sustain their powers. The birds have been weakened, and the effect on their health proved permanent. The 500-mile race is the favorite for long-distance birds, and 200 and 300-mile courses for the younger birds that have not yet won their laurels.

Besides being bred as pets and desirable companions the homing-pigeons are now being used for various services. It looks very much as if their services as war messengers would soon be dispensed with, for wireless telegraphy has made the pigeons superfluous, and the extensive pigeon lofts in the military and naval services of European nations will probably soon come useless

In peaceful pursuits, however, the homing-pigeons have in recent years become of great service. Country physicians have in many instances adopted them as messengers. A physician raises a loft of carriers for the pleasure of it, and when he visits a patient four or five miles away, he carries with him a basket containing one of his birds. If dangerous symptoms arise in the night or the following day, the pigeon is released Some physicians with long country with a message. routes carry a half a dozen or more of these pigeo on their rounds, and leave one at each place. report of the different cases can thus be obtained by pigeon service at no cost to physician or patient. This service has also been extended on the large Western Some farmers receive daily reports of the markets from the city in this way. There are no telephone or telegraph wires to send the messages; but the pigeons answer the purpose satisfactorily. All that is required is a trip to the city once a fortnight to carry back the birds, and some one in the city to write the reports and release the birds

ON THE WORKING OF COMBINED COHERERS.

In a paper recently read before the French Academy of Sciences, M. A. Turpain examines the behavior of a set of several coherers connected to the same antes sensitiveness of a coherer is determined by means of the distance over which a radiator is just capable of acting distinctly on the coherer. The distinctness of this action is given by the value of the current, which, after cohesion has been established, will traverse a very sensitive galvanometer. If the coherer be inserted in a closed circuit, its sensitive ness is found to be much higher than when in open in fact, at the moment of the emission of waves, one electrode only of the coherer is connected the antenna and to one pole of the cell, the current of which is intended to traverse it, while the other electrode of the coherer is insulated. This is started by connecting the insulated electrode of the col to the ground and to the second pole of the battery after the waves have been emitted. If several co ers be connected in shunt, one of the electrodes of each coherer being connected to the common antenna, while the other is or is not connected to the remainder of the circuit, the following facts are stated: The coherers will preserve the same relative set tiveness, both in open and in closed circuits. order to ascertain the sensitiveness of several ciated coherers, an emission of waves such that one coherer only is acted on, should be produced, all the

ird

few

rd's

get

the

able

iles

dis-

usly

from

way

wing

not birds ways

their

effect

race

e not

ions. rious es as

uous, naval

n begeons

m at

four

arise leased ountry

daily

This

e mar-

it the carry

RS. ademy

anten-ned by

is just he dis-of the

If the

n open

nnected

current e other started coherer battery i coher-of each antenna,

remain-ted: L e sensi-

2. In

hat one all the

Scientific American

coherers being in closed circuit. The operative coherer is next put in open circuit by insulating one of its electrodes, when another emission of waves is caused to act on the coherer left in closed circuit. After putting this second coherer in open circuit, the same process is continued until all the coherers to be classified have been dealt with. Experiment goes to show that the sensitiveness of each coherer is the same when used both separately and in connection with neighboring coherers experimented on at the with neighboring conerers experimented on at the same time. As regards, in the second place, coherers connected in series, if all the coherers be decohered, the circuit (coherers-battery-galvanometer-coherers) will include as many breaks as coherers. In order to ascertain the sensitiveness of each of the coherers, waves are produced by establishing conductive bridges connecting the mercury vessels, the distribution of which may easily be imagined, when each of the coherers taken apart is connected to the circuit (batherers taken apart is connected to the circuit (pat-tery-galvanometer), the degree of cohesion produced by the emission of waves being thus ascertained. The connection of an antenna with a coherer electrode will augment the sensitiveness of the latter. The point of contact between the antenna and a circuit, comprising several series-connected coherers, being varied, the sensitiveness of the coherer system is thus found to undergo material alterations. The results of this experimental investigation are applied first to constructing an apparatus for recording the course of thunder storms; and, second, to designing sensitive instru-ments which may be utilized both in wireless telegraphy and in Hertzian wave telegraphy with conductors.

FLEETS IN THE FAR EAST—AN ENGLISH REVIEW OF THE POSITION OF RUSSIA AND JAPAN.

BY ABCHIBALD S. RURD, OF LONDON, ENGLAND.

(Concluded from page 171.)

As the two powers are at present, Japan had the advantage at the opening of the war, and this has been greatly enhanced by her initial success. She possess greaty ennanced by her initial success. She possessess more ships, such as her six battleships and her eight armored cruisers, of first-class fighting power, while the value of one or two of the Russian battleships and armored cruisers is problematical. Moreover, the Japanese ships are well manned with officers and men of the highest intelligence and training, while Russia has the nignest intelligence and training, while Russia has hurried her ships out to the Far East inadequately manned, especially as to mechanical ratings, which are of supreme importance. This is the present situation. What will be the position six or eight months hence?

What will be the position six or eight months hence: Unless the present war is to be an unbroken succession of disasters, which is scarcely probable, Russia should at least hold her own on land, until the arrival of the five powerful battleships which are nearing completion in the Baltic yards. Her programme of shipbuilding of 1898 included seven first-class battleships. At present only two of these ships have been completed and sent to the Pacific, the "Retvisan" and the "Czarevitch," together with several armored cruisers. The five other battleships are nearly ready for sea. It is officially announced that they will be finished this year (1904) and unless the early disasters have caused a change in the Puscion plans all these vessels are to be disthe Russian plans, all these vessels are to be dis-patched at the earliest moment to strengthen the Far patched at the earliest moment to strengthen the Far Eastern squadron. According to the official programme the following reinforcements will be sent from the Baltic to Port Arthur to join Admiral Alexieff's command in the course of this year:

Five battleships—"Imperator Alexander III." "Borodino," "Orel," "Slava," and "Kniaz Souvarow."

Two cruisers of the second class—"Jemtchug" and "Izumrud," of 3,200 tons displacement and 22½ knots

Eleven torpedo boats.

The five battleships are of a most powerful type, displacing 13,500 tons of water, well armored, and armed with the following weapons of the latest manufacture

- 20 12-inch breechloaders.
- 60 6-inch quickfirers.
- 100 3-inch quickfirers. 100 3 pounders.
- 40 1 pounders.
- 20 torpedo tubes.

These fine ships are improvements upon the "Czare-vitch," which was illustrated recently in the Scientific Mich," which was illustrated recently in the Scientific American. It must be confessed that these ships represent most substantial reinforcements. Stated in the fewest possible words, their arrival at Port Arthur will signify that if she can repair her damaged battle-chips Russia has won, on paper, at least, the game she has played so skillfully for the past eight years. The "Imperator Alexander III." will be completed this tpring and the others during the year. It is officially appropriate that the three battleships and most of the anounced that the three battleships and most of the traisers injured at Port Arthur can be repaired; and the damages as detailed in Alexieff's report are not becausarily irreparable. If Port Arthur and Vladivo-Mock can hold out and the fleets remain under their suntil the five battleships arrive Russia will have stock can a overwhelming superiority in battleships.

But it may be asked what will be Japan's position six or eight months hence. As she is to-day, so she will be then. Her shipbuilding programme, undertaken at the close of the war with China, has been completed, and she has commenced the construction of no more armored ships. A project has been under discussion for two years, but financial difficulties have interposed to cause its postponement. Time can render this newest member of the concert of the powers no aid, and meantime Russia will be reaping the full advantage of the colossal naval expenditure on which she embarked in 1898. Should the Russian reinforcements succeed in reach

ing Port Arthur, she would have at least eleven and possibly thirteen battleships, and five armored cruisers possibly thirteen battleships, and five armored cruisers to oppose the six battleships and eight armored cruisers of Japan, and against such odds, unless the Russian personnel is hopelessly incapable, Japan could not fight with any hope of success. The Russian fleet will be far superior numerically at this date to the British Mediterranean squadron in armored ships, though not equal to it in fighting power.

Other powers do not maintain their navies for the

express purpose of guarding their interests in the Far East, and it is unlikely that any of them will make any considerable additions to their squadrons in the Pa-cific in the next few months. Great Britain, it is true, has sent out an additional battleship, the "Centurion," but it is impossible that with the claims on her resources for the defense of the Mediterranean, the Eng-lish Channel, and the North Sea, she can strengthen her squadron in the Far East much more. There is also little likelihood that either the United States, Germany, or France will materially weaken their position at vital points nearer home to add to the squadrons they now maintain in Chinese waters. It may be taken for granted that six or eight months hence the naval representation of the other great powers will be much the same as to-day. The strength of the several fleets is set out below in summary, the British and Russian reinforcements being included:

	Russia.	Great Britain.	Japan.	U. S.	Ger- many.	France.
Battleships	. 13*	5	6	3		1
Cruisers-						
Armored	5	2	8	2†	1	2
Protected	111	8	16	4	6	5
Torpedo craft	40	13	97		1 :	14
a Three of the		anhiban as			Atrobio.	a.

Three of these battleships are temporarily disabled.

†These two ships are coast service monitors.

† This is exclusive of the four cruisers sunk; but includes

ur that are temporarily disabled.

These brief details indicate inadequately the relainto relief the strong position which Russia will hold should she be able to maintain her position until her fleet has been reinforced. In St. Petersburg it is realized that while in Europe Russia must continue to be at considerable disadvantage, she can dominate Chinese waters with little fear of any other power interfering with her designs. Whatever the outcome of the present war, the eventual result of Russia's action cannot be prevented by the Island Kingdom because it has not the requisite staying and financial power and natural resources which will enable it to continue indefinitely its opposition to Russian designs. It may be of interest to append a complete list of the

fleets of the great powers in the Far East.

	GREAT BRITAIN.
Glory	(Admiral Sir Gerard Noel)
Albion	(Rear Admiral the Hon. A. G. Curnon. Howe) Sister battleships of 15 tons.
Ocean	
Vengeance	
Centurion	Battleship, 10,500 tons.
Стенву	Armored cruiser, 12,000 tons.
Leviathan	. Armored cruiser, 14,100 tons.
Amphitrite	First class cruiser, 11,000 tons.
Argonaut	First ciass cruiser, 11,000 tous.
Blenheim	First class cruiser, 9,000 tons.
Eclipse	Second class cruiser, 5,600 tons.
Talbot	Second Class Craiser, 5,500 tous
Sirius	Second class cruiser, 3,600 tons.
Thetis	Second class cruiser, 3,400 tons.
Fearless	Third class cruiser, 1,580 tons.
Phonix	
Algerine	Sloop, 1,050 tons.
Esplegle	*
Rinaldo	
Rosario	Bloop, 980 tons.
Vestal	Minobi and comm
Mutine	
Bramble	First class gunbost, 710 tons.
Britomart	
Kinsha	River steamer, 331 tons.
Moorhen	Second class gunboat, 180 tons,
Teal	Second ciano Bonosci, 100 comi
Robin	Second class gupbont, 85 tons.
Snipe	
Sandpiper	River gunbont, 85 tons.
Woodcock	Second class gunboat, 150 tons.
W COURSE E	
Six torpedo boa	t destroyers.

UNITED STATES. Wisconsin. . . . (Rear-Admiral R. D. Evans, commander-in-chief), battleship, 11,540 tons.

Wisconsin. . . . (Rear-Admiral P. H. Cooper, commanding Northern Squadron), battleship, 11,565 1668.

Oregon	. Battleship, 10,288 tons.
Monadnock	Montan 4 007 ton-
Monterey	Monitor, 4,005 tons.
Albany	
New Orleans	Second class cruiser, 3,769 tons.
Raleigh	
Cincinnati	Second class cruiser, 3,213 tons.
Isla de Cuba	Gunboat, 1,125 tons.
Wilmington	Gunboat, 1,397 tons.
anerena	
Annapolis	
Vicksburg	Sunboat, 1,000 tons.
Don Juan of	
Austria	Gunboat, 1,130 tons.
	. Junboat, 347 tons.
	Gunboat, 250 tons.
	. Gunboat, 600 tons.
	.Gunboat, 51 tons.
	Gunboat, 210 tons.
	.Converted yacht, 607 tons.
Rainbow	.(At Cavite, Rear Admiral Yates Stirling).
	distilling white

In addition there are two colliers, the Justin and Pompey:

two tugs, the Placalagua and Wompatuck, and the sugships Zaffro and Nanshan.	pply
PRANCE.	
Redoubtable Battlewhip, old, 8,767 tons.	
Vauban Armored cruiser, old, 6,150 tons.	
Montcalm (Vice-Admiral Marechal), armored crul 9,516 tons.	ser,
Chateaurenault. First class cruiser, 8,018 tons.	
Bugeaud Second class cruiser, 3,722 tons.	
Pascal Becond class cruiser, 3,985 tons.	
Acheron Armored gunboat, 1,640 tens.	
Surprise	
Vigilant Gunboat, 123 tons.	
Decidee Gunboat, 646 tons.	
ArgusGunboat, 123 tons.	
CometeGunboat, 473 tons.	
Caronade Gunboat, 140 tons.	
Bengall Dispatch vessel, 547 tons.	
AlouetteDispatch vessel, 506 tons.	
Furst Bismarck (Bear-Admiral von Prittwitz), armo cruiser, 10,650 tons.	red
Hansa	0.00
Bertha Becond class cruiser, 6,100 tons.	
Thetis Third class cruiser, 2,645 tons,	
Grier Third class cruiser, 1,776 tons.	
Bussard Third class cruiser, 1,580 tons.	
ITALY.	1
Vettor Pisani Armored cruiser, 8,500 tons.	
Elba Second class cruiser, 2,780 tons.	


SCIENCE NOTES.

A Russian naturalist has made a series of measurements, by a thermo-electric method, of the temperature of insects. A few of his results are noticed below. The temperature of the human body, it will be remembered, is essentially the same in the tropics and in the polar zones. Insects at rest have a temperature essentially the same as that of the surrounding air in ordinary conditions of heat and of humidity. Under usual conditions the temperature of an insect rises with that of the surrounding air, only more slowly. When that of the surrounding air, only more slowly. When the air is very moist the insect's temperature may rise more rapidly than that of the air. When the insect begins to move, its temperature rises and continues to rise until the motion ceases. This rise of temperature continues till at about 38 deg. C. (102.2 deg. F.) a heat paralysis sets in. The paralysis is only temporary; it ceases as the temperature falls once more. Below —0.5 deg. C. (31 deg. F.) insects are perfectly without motion. The temperature must, in general, be raised to 12 deg. C. (53.6 deg. F.) before the wings are moved. For one species—Saturnia pyri—the highest temperature compatible with life is 115 deg. F. This is about the temperature that is fatal to vegetable life.

For some time past prussic acid has been considered to be the most deadly poison extant. Mr. Lascelles Scott, of Little liford, England, however, has now discovered a far more deadly poison—the substance scientifically known as di-methylarsine cyanide, or more familiarly as cyanide of cacodyl. Three grains of this substance diffused in a room full of people would kill all present, so powerful is it. So deadly is this poison, that it is highly dangefous to handle it. It is a white powder melting at 33 deg. and boiling at 140 deg. When exposed to the air it emits a slight vapor, to Inhale which is death. Mr. Lascelles Scott has experiently deadly assured the deadly neture of this roton, for while he enced the deadly nature of this poison, for while he was assisting Sir B. W. Richardson in the compilation of his work "On the Causes of the Coagulation of the Blood," he tried its effect upon animals. One-millionth part of cyanide of cacodyl in the atmosphere of an air-tight cage killed a dog almost instantaneously, and then its power was by no means exhausted, for a sec-ond, third, and fourth dog placed in the same cage, instantaneously died from the effect of that single in-finitesimal dose. Although so little of the properties of this poison are known, it was first made many years ago. Cadet, the famous French chemist, by combining acetate of potassium with white arsenic, produced a fuming liquid which, although he did not know it, was oxide of cacodyl. The German chemist Bunsen com-bined this with cyanogen, a radical of prussic acid, and made cyanide of cacodyl, the formula of which is

ROTARY VALVE FOR SAWWILLS

An improved form of rotary valve has recently been vented by Mr. Randolph Gillette, of Little Falls, Minn. This valve is particularly adapted for use on sawmills and embodies means for quickly shutting off the live and exhaust steam at the same time when deed, thus bringing the carriage almost instantly a stop, and effectually preventing it from running



ROTARY VALVE FOR SAWMILLS

Furthermore, the revoluble valve plug is arranged to prevent unequal expansion and contraction, which would distort it and cause it to bind. In our illustration we show one end of a steam cylinder with the rotary valve attached thereto. A similar valve with the exception of a slightly different arrangement of the ports, as shown in the lower left-hand sectional view, is attached to the opposite end of the steam cylinder. These valves are connected to a common live steam pipe and are also controlled by a common lever. As more clearly shown in the section views, the steam is admitted to two ports in each valve casing, one at each side of the revoluble cylinder plug. A shaft passes through the center of the cylinder plug and on this, at each end of the cylinder, a hub is mounted. To allow for contraction and expansion the cylinder plug is not directly connected to these hubs, but is scured by pins to webs formed thereon. The cylinder plug opens at the ends into steam passages which connect with the steam cylinder above. The exhaust port is shown at the bottom of the casing, and may be connected with the steam cylinder through either two ports oppositely disposed in the cylinder plug. Similarly the live steam ports may be connected with the steam cylinder by bringing into register with them two ports lying between the exhaust ports in the cylinder plug. It will be observed that the valve may e turned to cut off the steam from the steam cylin der, at the same time opening the exhaust port; or, further turning the valve in the same direction, or

reverse movement of the valve, both the inlet and exhaust ports will be closed. If a workman finds that he cannot stop the steam feed by operating the controlling lever backward, he may drive it forward, and thus stop the feed, or, if the carriage is moving backward, and he cannot caus the lover to move forward, he can drive the lever backward in the same direction and

THE ADAM-BOUDIN GLOBULAR BOAT.

Evidently the roller boat idea is hard to kill. The continental papers have been illustrating what is considered a new type of craft which goes by the name of the "Adam-Boudin self-propeller." The boat boat. from what we have been able to gather, con-sists of two concentric spheres, the inner of which, containing a 24-horsepower motor drives the outer sphere. Vanes are provid ed on the outer sphere, for the purpose, we presume, of securing some kind of a hold on the water. The motor has four speeds The inventor high hopes for his craft. He confidently

Scientific American

assures the representatives of the foreign press that he will be able to make 50 kilometers (31 miles) an hour with his boat. For our illustrations we are indebted to the London Illustrated News.

How Baby Bats are Nursed.

"Ever since the days of Pliny." writes Mr. R. Lydekker in Knowledge, "It has been a matter of com mon knowledge that female bats are in the habit of carrying their helpless young about with them during their aerial flights for some time after birth. With the exception of one peculiar species, the young bat always clings to the under surface of its mother's body, where it obtains a secure hold among the den of fur. The precise position in which the young bat supports itself when its parent is in flight does not appear to be recorded. the older observers it was generally sidered that bats commonly produced two young at a birth, as is testified by Pliny, who wrote that the female carried her twin offspring about with her. Later observations, however, led to the conclusion that this idea was errone ous, and that as a rule only one is produced The late Dr. G. E. Dobson at a birth. . his time the greatest authority on noticed that in certain species of fruit-bats the nipples of the males were much enlarged during the breeding season; and from this circumstance he started an entirely novel idea which is expressed in the following sentences: 'It is probable that where two young are born at a single birth, the male relieves the female of the charge of one (as the weight of two might render flight difficult or impossible), and at the same time performs the office of a nurse It is well known that many species of bats have occasionally two young at a birth, but I have never found a mother with more than one clinging to her body. The size of the pectoral teats in many male specimens (though in none yet observed by me so large as in this species and in another case referred to above) led me to think that instances of the male performing the office of nurse are probably not uncommon

among bats.' Whether this suggestion is true of fruitbats must be left for future observation to determine but it is now practically certain that it will not hold good for the ordinary insectivorous bats; although, so far as I know, no case has hitherto been recorded where a female of any of the European species of bats has been actually seen carrying about her twin offspring. The interest that would attach to a wellauthenticated instance of this nature may be com-mended to the attention of the readers of Knowledge. If, however, instances of female bats carrying more



The Boat Entering the Water.




The Boat on Shore

A GLOBULAR VESSEL

than one baby offspring clinging to their bodies are unknown in Europe, they have recently been brought to light in America. And in these instances not only has the parent bat been seen loaded with the of twins, but actually with that of a quartette.

VALVE FOR CONTROL OF HYDRAULIC ELEVATORS

A patent has recently been granted to Mr. Joseph Utrilla, of 205 Second Street, Jersey City, N. J., for an improved form of valve particularly adapted for use in controlling the motive agent for hydraulic or similar elevators. The valve is very simply con-structed and may be readily and quickly operated. A perspective view of the valve in section and the ge



VALVE FOR HYDRAULIC ELEVATORS

ng by which it is operated is shown herewith, also a transverse section taken through the center of the By comparing these two views the simple construction will be readily understood. The valve proper sists of a drum with a large opening at the bottom, and a smaller opening at one side. Passing trans versely through the drum is a tubular port of oval cross section, which is designed to communicate with inlet and outlet ports in the side walls of the valve casing. The valve proper rests upon a wear ring in the bottom of the casing, and extending upward from the valve through a stuffing box on the top wall of the casing is a valve stem having a segmental bevel pinion on its end engaging with a segmental bevel gear on a shaft supported in bearings attached to the valve casing. Mounted on this shaft is a cable wheel by which the valve is operated. A counter-weight is attached to the cable wheel for automatically moving the valve to closed position upon releasing the cable pressure. In operation, when the valve lies in such position as to bring the tubular port in line with ports in the valve casing, pressure is admitted to move the elevator upward. By moving the valve through an angle of 45 degrees the tubular port is thrown out of register with the ports in the side w of the valve casing, as shown in the transverse-section view, and the pressure is thus cut off and the elevator stopped. To cause downward movement of the elevator the valve is turned through a further angle of 45 degrees, bringing the port in the side wall of the valve drum into communication with the outlet port of the valve casing, thus permitting the water other motive agent to pass back through the outlet port, and thence through the ports in the side wall and the bottom of the valve drum and out through the port in the bottom of the valve casing. It will be noted that the whole movement of the valve is in the space of 90 degrees; therefore, it may be

quickly operated in both directions

The "blue ground" in which diamonds are found at the De Beers and Kimberley mines is called by Dr. Stelzner a "breccia." Most of the angular-edged or rounded fragments of this breccia are composed of a greenblack or blue-black serpentine-like Fragments of rock which are found in Karoo formation—such as sandstone, shale, and diabase—are to be found in the "blue ground." There are also other rocks, in the shape of bowlders, which are not known in the Karoo formation, and which doubtless come from a greater depth, possibly from the rocks upon which the Karoo beds lie. The mass of the "blue ground" consists of olivine, more or less changed by oxidation, the following minerals: Chromic dialiage, bronzite, pyrope containing chromium, flesh-colored zircons (locally called Dutch bort), cyanite, biotite, chromite, titanium, magnetic iron, and, finally, small crystals of perofskite.—The Engineering Record.

....

THE LARGEST PHOTOGRAPH IN THE WORLD.


At the recent Dresden Exhibition of German Civic Life, the Neue Photographische Ges. Berlin Steglitz exhibited a photograph which is said to be the largest ever taken. This gigantic picture measures 12 meters by 1½ meters (39 feet 8 inches by 4 feet 11 inches). Another copy of the photograph will be exhibited at the World's Fair by the Rotograph Company, of New

The photograph represents the Bay of Naples, and was taken from Castel San Marino, the highest point behind Naples, from which the eye commands the Scientific American

whole city and bay as far as Mount Vesuvius and Capri. In order to secure as extensive a panorama as possible, six different views on as many plates, measuring 21 x 27 centimeters (8.1 inches x 10.5 inches) were first taken. From these six plates, which were designed with a view to being connected to one another in a continuous series, six enlargements, 1½ x 2 meters (4 feet 11 inches by 6 feet 7 inches) in size were prepared by means of an apparatus with a lens 32 centimeters (1 foot) in diameter. The enlargements were made directly on silver bromide paper. The inherent difficulty of connecting the single plates so as to avoid any break was overcome so successfully whole city and bay as far as Mount Vesuvius and

that it is practically impossible to detect the boundary line of any two plates. According to their character, the six negatives were exposed for unequal periods, varying between ½ and ½ hours.

In order to develop the picture, a huge wheel was made of specially prepared wood. The wheel was 4 meters (13.12 feet) in flameter and 1.75 meters (6.5 feet) in breadth, the periphery thus being 12½ meters (41 feet), and containing 90 slats intended for receiving the photographic paper. There were further used three large tanks about 70½ cubic feet in capacity, intended respectively for the developing, clearing, and fixing solutions, acetic acid and sodium hydroxide




The Photograph During Development.



Preparing the Developing Bath.



Retouching the Pinished Photograph.



Unrecking the Print into the Clearing Bath. MAKING THE LARGEST PHOTOGRAPH IN THE WORLD,

lso a con roper ttom, rans oval with valve from f the bevel bevel o the wheel

ht is

4.

are

only

RE, oseph , for

aulic con-l. A gear-

oving cable such h the ed to rt is walls ection vator vator of 45 port er or wall h the

s are Most green-Karoo and
"blue
n the
wn in
btless

n the

from s lie. sts of ation, romic hrom called omite.

solutions. Each tank could be shifted about on five tron wheels moving along rails 16 meters (52.48 feet) in length. A gigantic water tank, 15 meters (49.2 feet) in length, 2 meters (6.56 feet) in breadth, and % meter (2.46 feet) in height, having a total capacity as high as 476.68 cubic feet, was further used.

On account of the large developing wheel employed, the paper was developed by night in the open air. Before developing the picture, the exposed paper, fitted with a protecting cover, was laid over the slats of the wheel. The wheel was then set rotating. As it turned, it dipped the lower part of the paper into the developing liquid. The light portions were especially treated with sponges impregnated with energetic developers. Portions whose development was too rapid were checked by means of iced acetic acid solutions. An iron oxalate developer was used.

An iron oxalate developer was used.

After first interrupting the developing process by projecting iced acetic acid on the photograph by means of a hand pump, the paper was conveyed into an acetic acid bath, where the clearing process was completed after twenty minutes' time. The picture, after an intense rinsing, was transferred luto the fixing bath, where it remained three-quarters of an hour. After another rinsing the photograph was thence conveyed into the large washing tank above mentioned, where it remained for about eight hours, while a continuous supply and withdrawal of water took place. The total consumption of water used in washing the print was about 10,592 cubic feet.

After the water was drawn off, the picture was stretched out on wooden bars attached to the upper edge of the tank, where it remained for about ten hours before it was completely dried.

SAMUEL PIERPONT LANGLEY.

It is safe to say that no just estimate of the very eminent and useful pioneers of the physical sciences for the past several decades would fail to include Samuel Pierpont Langley.

Born in Roxbury, Mass., August 22, 1834, Mr. Langley was graduated from the Boston High School in 1851, thereafter took up the study of civil engineering and architecture, and subsequently practiced these professions, furnishing an instance of a certain tendency among men of attainment to believe in and utilize a minor talent in the beginning as the working field for a career. But his interest in astronomy was innate, and the time saved from the demands of engineering and architecture went to the study of that science. Parts of the years 1864 and 1865 he spent in European travel, visiting foreign observatories and learned institutions, to return bent upon devoting his life to scientific pursuits. The practice G. architecture had imbued him with a keen æsthetic sense and powerful constructive imagination. No one better enjoys the beautiful solution of a problem. This fine sense of proportion, but more especially the faculty of creative imagination, modern astronomy and physics both demand as the working basis for success.

demand as the working basis for success.

In 1865 he became an assistant at the Harvard College Observatory, and the following year was appointed Assistant Professor of Mathematics in the United States Naval Academy at Annapolis. Within the same year he became the director of the new Allegheny Observatory at Pittsburg.

It was here that he found opportunity for one of the few directly utilitarian services ever rendered by astronomy—the establishment in connection with the Pennsylvania Railroad Company's telegraphs, of the now familiar system of the standard time service by telegraphic signals. At that time (1868) the use of local times was universal in this country, even by the railways, and confusion or accident was frequent and inevitable. By these signals this confusion was stopped over the whole area from the Atlantic seaboard to the Great Lakes. The system was at once widely imitated.

Mr. Langley's interest in pure astronomy was now rapidly developing into a greater interest in astrophysics, and he began the well-known series of researches upon the sun and the physics of the solar radiation with which his name has been most intimately associated. In 1869, in 1870, and in 1878 he had charge of government eclipse expeditions, of which the latter, to Pike's Peak, resulted in determining a hitherto unsuspected extent of the corona. His work upon sun spots, extending over this period, is too well known to need mention here, except to call attention to the remarkable accuracy of observation, as well as the skill of draftsmanship, which renders his drawings of sun-spot phenomena made before the days of solar photography, perhaps the final statement of what the eye can see of the surface of the sun.

About 1875 he began to devote much attention to the heat spectra of the sun and other hot bodies, and as an aid to that research he in 1880 devised the bolometer, probably the most useful and delicate instrument for the measurement of radiation.

To this period, and as part of the general research upon the sun's physical relation to the earth, belong the important preliminary papers on the energy spectrum of the sun, the transmission of the earth's atmosphere, on the Solar Constant, the behavior of
prisms toward radiations of long wave-length from
bodies at low temperatures, the energy-spectra of
heated terrestrial objects, and the energy spectrum of
the moon. The moon's heat had hitherto been barely
recognized by the thermopile, but with the bolometer
Mr. Langley was able to analyze minutely the details
of its spectrum.

During these researches at Allegheny he had become convinced that there was a great, and then unsuspected, selective absorption of the sun's energy both in the sun's and the earth's atmosphere. Again successful in obtaining the aid of the government, he organized in 1881 an expedition to the top of Mount Whitney, in California, the abrupt heights of that lofty peak permitting observations to be made from two stations geographically close together, but separated by more than two miles of altitude. The result of the observations made became the basis for an entire change in the hitherto accepted value of the Solar Constant, as determined by Poulilet's methods, and the reversal of the old belief that the atmospheric absorption was greatest in the red end of the spectrum.

Mr. Langley was now fairly embarked upon a monumental task, not yet fully completed, requiring unusual niceties of observation and deduction. This was the exploration and mapping of the great unknown region of the solar spectrum lying beyond the visible red light, and in which region fall the wave-lengths of the far greater part of the heat-energy lavished upon the solar system. To the study of the visible spectrum the science of chemistry is under a vast debt, and upon it is largely founded all modern knowledge of stellar systems other than our own. Photography had revealed the invisible region beyond the violet, but wave-lengths of only one-tenth the range he had by 1885 demonstrated to exist were under study by these means.

In 1887, at the beginning of this research, Mr. Langley became secretary of the Smithsonian Institution, which officially represents the interests of the United States in pure science.

It is here that Mr. Langley has most conspicuously shown the characteristics which had early marked him for an eminent career. Without an executive intellifor an eminent career. of a high order, the workings of the institution must have suffered a decline from the high plane of usefulness inaugurated for it by Prof. Joseph Henry, and carried on by Prof. S. F. Baird, whose administration had preceded Mr. Langley's. The institution has expanded in all of its activities under his charge, and his fitness to control a complex system of subordinate bureaus and men has been salient. As the head of the institution, his ability to present to Congress the needs of the sciences in this country has been of great service, and it is due largely to his efforts that the institution also administers private appropriations for scientific ses, and has attracted large bequests to be devoted to similar ends.

These duties have necessarily occupied much of his time, but he has continued to give his personal direc tion to the Astrophysical Observatory, which has been most steadily engaged in the investigation of infra-red spectrum. Here also were carried out a series of comparisons (with the bolometer) of the heat-energy emitted by various natural and artificial sources of light, with that of fire-flies and glow-worms, to demonstrate their relative efficiencies. It was here that, in 1892, the instrumental equipment was brought to include the automatic mechanism whereby the rela-tive movement of the bolometer in the spectrum, and of a photographic plate past the beam of light re-flected from the mirror of the galvanometer, were very accurately related, so that the infra-red spectrum could be quickly explored, and a photographic image of its energy-curve recorded. Much valuable minor research in optical physics, as well as in instrumental design, has been here accomplished. Mr. Langley directed a very completely equipped expedition from this observatory to Wadesboro, N. C., for the observation of the eclipse of 1900, which resulted in an interesting determination of a value for the radiation from the corona, and some remarkable photographic observations.

After Mr. Langley became the head of the Smithsonian Institution, he was enabled to begin that series of efforts to solve one of the greatest of human problems—that of mechanical flight—which has lately attracted such widespread popular interest in this country. His interest in flight dates from boyhood, and it has long been his belief that the true course for the solution of this problem lies initially in the result of a research into the conditions surrounding the behavior of heavy bodies in motion through the air, rather than in immediate experimental attempts at flight. It has been his aim then, in inaugurating any work whatever in this direction, to establish, first of all, with such accuracy as the resources of refined physical measurement and diligent experiment could produce, the conditions which would surround the final mechanical solution. He took up the subject seriously in 1889, and in 1891 published his "Experiments in

Aerodynamics" and later, after unceasing experi-Aerodynamics" and later, alter ament he was enabled to print the larger theory in a ment he was enabled to print the larger theory in a ment he was enabled "The Internal Work of the Wind." This preliminary work satisfied him of the possibilities of echanical flight, and under the great discouragements of what will perhaps ultimately be recognized as the most difficult branch of mechanical engineering, he commenced and for several years carried on the actual construction of experimental flying machines upon the principles which had been developed in his private workshop at the Institution. In 1896, for the first time in history, a mechanical structure, free of any attachment to the ground and wholly without any supporting power but its own engines, made several flights of over one-half mile each. Mr. Langley at this point reached the original aim of his researches this direction-that of demonstrating, as a of mechanical engineering, first, the conditions for and second, the possibility of accomplishing, mechanical flight. It was only later, the necessities of the military branch of the government indicating the need of a demonstration of the practical possibilities of flight, that Mr. Langley determined to go on with those experiments, which are so well known to the newspaperading public, and which have so far brought of negative results. It may be said in passing that it re quires moral courage of a high order for a man already secure in popular estimation as a savant to attempt to build a flying machine, since the effort is sure of ridicule by a large section of the unthinking public, which sees no merit save in absolute success.

It is difficult to speak of Mr. Langley apart from

It is difficult to speak of Mr. Langley apart from his work. The two are inseparable. Yet the esthetic sense mentioned as one of his chief characteristics finds outlet in a very wide reading, by no means confined to scientific literature. Added to his capacity to recuperate from the cares of his work by travel, which is perhaps his chief amusement, Mr. Langley is a member of the Metropolitan and Cosmos clubs in Washington, of the Metropolitan and Century clubs in New York, and of the St. Botolph Club in Boston, and may frequently be found at one or the other of their houses, or enjoying the game of golf at some country club.

Foreign institutions and scientific bodies have showered upon him degrees and honors. He has received the degrees, D.C.L., of Oxford; D.Sc., of Cambridge; is a foreign member of the Royal Society of Great Britain, correspondent of the Academy of Sciences, Institute of France, and Fellow of the Royal Institution; he has been awarded the Janssen medal by the Institute of France, and the medal of the Scientific Society of France, and the Rumford medal by the Royal Society of London; while at home the universities of Harvard, Princeton, Michigan, and Wisconsin have given him the degree of LL.D. He was president of the American Association for the Advancement of Science (1887), and has been awarded the Henry Draper medal and the Rumford medal by the National Academy of Sciences of the United States, of which body he is a member.

Mr. Langley's published writings include over one hundred titles. It is not the least of his important qualifications as an investigator, that he writes with conspicuous clearness and in an English style which enlivens the driest statement.

A 63-Mile Fence.

According to the Kansas City Journal, one of the longest fences in the Northwest is being constructed, running entirely around the Lower Brule Indian Reservation, on the Missouri River, in the central portion of South Dakota. This remarkable fence will be sixty-three miles in length. It is composed of four wires placed on posts set a rod apart, cedar and ash posts alternating. In its construction 250 miles of wire will be used, or 76,000 pounds. To erect the fence required an aggregate of 19,000 posts. In this long fence there will be only three gateways, which will be guarded when the fence is completed.

The fence is being constructed by the Indians themselves under the direction of the agency authorities, the Indians receiving \$2.50 per day for man and team and \$1.25 per day for men. It is understood that next spring the government will issue stock cattle to the Indians, to be grazed inside this huge inclosure, the purpose of the government being to encourage the Indians in stock-raising so that they can ultimately support themselves.

Andrew H. Bergstrom, of a firm of contractors at St. Louis, has agreed with the Swedish World's Fair commission, to put together their national pavilion free of all cost. The building was erected at Stockholm and has been shipped to St. Louis in sections. Mr. Bergstrom estimates that it will require the services of 150 men three days to put the building together.

^{*} Smithsonian Publication No. 801

[†] Smithsonian Publication No. 884.

Correspondence.

Our Youngest Old Subscriber.

To the Editor of the SCIENTIFIC AMERICAN:

I notice under the head of "Correspondence" in this week's issue of the Scientific American that A. C. L. takes great credit to himself for having been a reader of the Scientific American from the time when he was seven years old to the present, when he is thirty-five. The writer of this has been a reader of your paper under the same conditions mentioned in A. L's article from the time he was six years to the ent, when he is forty-three. JRF

Dayton, Ohio, February 20, 1904.

Artificial Cooling and a New System of Heating. To the Editor of the SCIENTIFIC AMERICAN

The subject of artificial cooling is one of those that each summer arises anew and figures among the few that are felt as an incongruity in our age of high tech nical advancement. That an electric desk or ceiling fan does not only not cool the atmosphere of an inte rior, but helps to heat it through its rapid motion, is well enough known, but strong artificial draft continuously interchanges the hot air, immediately surrounding the human body, for cooler air and accelerates the evaporation taking place, especially on faces, thus creating the sensation of cooling with which satisfy ourselves.

Why are interiors not cooled effectively and in the same way as in heating? Cold, in the shape of ice, is a market article, very common and very cheap, and which is brought daily to everybody's house dred pounds of it cost 20 cents, and with that amount 57,000 cubic feet of air can be cooled from 90 deg. F. down to 70 deg. Such an expense apparently would be no hindrance to the practical introduction and general use of ice for cooling restaurants, residences, or any other interiors. But what has prevented up to the present time the utilization of ice for that purpose is the lack of the proper means for transferring the cold from the ice to the air. Experiments on a large scale ducted during last summer in cooling a store at 553 River Street, Paterson, N. J., have enabled the writer to convince himself and others of the perfect feasibility of the plan to cool any premises by the use An apparatus of extreme compactness, consist ing of one or more segments, each of which represents an actual cooling (radiating) surface of 275 feet with but 6 cubic feet of space-displacement cools the air driven therethrough by a blower, before deliv ering it to the locality to be cooled: where cold spring is at disposal this will be sufficient to assure satisfactory results.

Any premises provided with such a cooling plant may with advantage be heated in winter by the very same means, i. e., the same apparatus and the same ducts, adding only a simple hot water heater and omitting the use of a fan. Such a system of heating would then coincide in principle with the well known ot air furnace heating, however, without the latter's drawbacks of possibly overheating the air or deterforating it in consequence of a leak in the furnace.

Paterson, N. J. G. EPPRECHT.

The Sportsmen's Show.

The annual New York Sportsmen's Show opened in Madison Square Garden on the evening of February 19, and will be kept open till 11 P. M. on that of March 5. The great attraction this year is a large rectangular tank in the center of the garden, moored to the sides of which are the launches and automobile boats various exhibitors. No less than speed launches or automobile boats are exhibited, besides an equal number of small launches. Numerous launch motors are also on view. Exhibits of various birds and animals are located on the ground floor, besides a most interesting exhibit of salmon and trout egs and fry. On the arena platform is a tank of water over which the fly-casting contests are held. while the exhibits of several sporting goods firms are also displayed there in rustic booths. The concert ball contains an exhibit of motor bicycles, one of which, with its motor cut in half longitudinally, is shown operated by an electric motor. An operating sectional model of a two-cycle launch motor is also shown in

The armor manufacturers of the United States, in rdance with promise, have added to their facilitics, and deliveries amounting to 11.493 tons have -a marked increase over any previous year We learn from the Iron Age that armor plates are now tested with capped projectiles. The acceptance tests for armor-piercing projectiles have been made rigorous, it being now required that they shall, at a prescribed velocity, perforate unbroken a plate of hard-faced armor equal in thickness to the diameter of the projectile, and then be in a condition for burst-

Scientific American THE HEAVENS IN MARCH.

With the departure westward of the bright winter constellations, the skies are becoming duller, especially as there are no conspicuous planets now visible in the evening; but the western half of the visible heavens is still very fine.

At 9 o'clock in the evening in the middle of March, Orion is still in sight, fairly well up in the southeast line of his belt is nearly horizontal, and points to Aldebaran on the right and Sirius on the left. The Milky Way, strong with bright groups of stars, lies above these constellations.

Starting almost below the Pole-star, we come first to the zigzag line of Cassiopeia. Next is Perseus, whose configuration is familiar to many who watched the fading of the new star of 1901. Auriga, with the brilliant Capella, follows, and then comes Gemini, whose two brightest stars. Castor and Pollux, lie considerably above the galaxy.

The still brighter star farther south is Procyon, in Minor. South of this is a vacant region, beyond which appear some stars of Argo—a fine constel-lation, which can only be seen to advantage in the southern hemisphere.

The contrast is great when we turn to the e sky. The Dipper in Ursa Major and the Sickle in Leo are the only conspicuous groups near the meridian. Below the latter lies Hydra, a long irregular line of stars extending from a small group east of Procyon clear to the southeastern horizon. The small quadrangle of brightish stars low in the southeast is Corvus, which certainly bears no resemblance to the Raven it is supposed to represent, while Hydra is a pretty fair serpent.

Above this, and south and east of Leo, is Virgo, with one bright star, Spica, and a wide curve of five pretty bright ones between the latter and Leo. Farther north is Bootes, with the brilliant Arcturus, and sev-eral second and third magnitude stars. Draco, which is on the right of the pole, and Ursa Minor, inclosed in its coils, are the only other notable constellations in sight.

THE PLANETS.

Mercury is evening star until the 26th, when he passes through superior conjunction—behind the sun —and becomes a morning star. He is invisible to the naked eye throughout the month, as he is very near the sun, and also south of him for most of the time. Venus is morning star in Capricornus, Aquarius

and Pisces. She is much less conspicuous than at the first of the year, being farther south and less than half as bright. However, she is still easily visible be-fore sunrise, as she rises at about 5 A. M. in the middle of the month.

Mars is evening star in Pisces, and can still be seen after sunset rather to the south of west, as he sets more than an hour later than the sun. His brightness is greater than that of the Pole star, and he is much the most conspicuous object in that part of the sky, next to Jupiter, which in the early part of the month is a few degrees below him.

Jupiter is also in Pisces, and is evening star until the 27th, when he is in conjunction with the sun, and becomes a morning star, just as Mercury does a few The two planets are in earlier. about the same time, but they are so near the sun that they are quite invisible.

Saturn is morning star in Capricornus, and is once more fairly visible. At the end of the month he rises

about two hours before the sun.
On the night of the 7th he is in conjunction with Venus, which is one-third of a degree to the north of him. The pair of planets should be easily visible in the southeast before sunrise.

Uranus is in Sagittarius, and is in quadrature with the sun on the 20th, coming to the meridian at 6

Neptune is evening star in Gemini. He is also in quadrature, on the 23d, but, being east of the sun, is due south at 6 P. M.

THE

Full moon occurs at 10 P. M. on the 1st, last quarter at 8 P. M. on the 8th, new moon at 1 A. M. on the 17th, first quarter at 4 P. M. on the 24th, and full moon again at 8 A. M. on the 31st. The moon is est the earth on the 1st and 29th, and farthest away on the 14th. She is in conjunction with Uranus the 9th, Saturn on the 13th, Venus on the 14th, Mer-cury on the 16th, Jupiter on the 17th, Mars on the

18th, and Neptune on the 24th.
At 8 P. M. on the 20th the sun crosses the celestial nator, and enters the sign of Aries, and in the phrase of the almanacs, "Spring begins.

On what is for us the night of March 16, but in Asia daytime on the 17th, there is an annular eclipse of the sun. It is of course invisible in America, but is an important eclipse in Madagascar, India, China, the Philippines, and the Malay Archipelago. The track of central eclipse passes just north of Madagascar, touches the north end of Sumatra, crosses part of Siam, and the extreme northern end of the Philippine

The excess of the sun's apparent diameter over the oon's is unusually great, so that the annular pi of the eclipse lasts at maximum for more than eight minutes. An eclipse of the sun is frequently accountly panied by one of the moon, a fortnight earlier or later, but this is not the case now, for at the previous full moon the moon passes just south of the edge of the earth's shadow, and at the subsequent one just north of At the time of the present solar eclipse, however, moon is almost exactly between the earth and sun, so that her shadow falls on the earth's equatorial regions. If she was farther north, so that her shadow fell in the Arctic regions, she would be farther south at the ensuing full moon, and would enter the earth's shadow psed (partially at least). In general, we that a solar eclipse which is central in and be eclipsed (partially at least). the equatorial regions will not be accompanied by a lunar eclipse, while if one is visible near one of the poles, there will be a lunar eclipse at the pre-ceding or following full moon (which one depends on whether the moon is moving north or south at the

An exceptionally good chance of observing an occultation of a star by the moon is afforded of March 22, when the bright star Aldebaran is or culted. As seen from Washington, the star disappea behind the moon's dark limb at 8 o'clock, and reappears on the other side at six minutes past 9. Th times of the immersion and emersion will be different at each place of observation.

As the moon is in her first quarter, her dark limb will be sufficiently illuminated by the "earth-shine" to make it visible, and one will have fair warning of the star's disappearance. The disappearance of such a bright star can be observed even with the naked eye, it a field-glass is a valuable aid, and a telescope still The reappearance is much harder to ol better. for unless one knows just where the star will re-appear, it is hard to pick it up when it first comes out.

The most striking feature of the star's disappearance is its absolute suddenness. It vanishes instantly. As is well known, this is the strongest proof that the moon has practically no atmosphere, for the refraction of an atmosphere would delay the star's disap-pearance, and make it gradual. Such gradual disappearances of a star's light have been observed, but many cases have later been explained by the discovery that the occulted star was double

Cambridge University, England.

The British International Cup Bace for Motor Boats. The Automobile Club of Great Britain and Ireland

as extended the time for receiving entries for international cup race to June 30, 1904, and the Automobile Club of America will receive entries up to June 1. If the entries are so numerous as to make it necessary to hold eliminating trials, in order to de termine which three boats shall represent America, these trials will be held shortly after the latter date. The race will take place in the Solent on July 30.

This race is to be held annually for a trophy presented by Mr. Alfred Harmsworth. Not more than three competing boats can represent each and each competing boat must be constructed wholly, in every particular, in the country which it repre The boat must not be longer than 40 feet over all, but there is no restriction as to the number, size, or horse power of its motors. These must be sufficiently powerful to drive the boat astern at four knots an hour in still water, and to drive it over the entire course at an average speed of at least 12 knots course must be in sheltered waters of the co olding the cup, and it must be from 6 to 12 nautical miles in length.

In addition to the two Napier boats entered in the English eliminating trials, J. R. Hutton, Ltd., has entered three 40-foot racers fitted with six-cylinder motors having a bore and stroke of 6.889 and 6.299 inches respectively and said to develop 170 brake horse power at 1,200 revolutions per minute. The total weight of the motor is 1,500 pounds. The Messrs. Thornycroft and Lord Howard de Walden, have also entered boats in these trials.

France will also be represented by a strong team. Among the entries already made in that country are A. Clement's and Pitre & Co.'s gasoline boats, an Gardner-Serpollet steam launch. It is hoped that Ger-many and America will also be well represented.

The estimated capacity of the new blast furnace plants to be started in the United States in 1904 is about 2,000,000 tons, and of this quantity it is computed that 905,000 tons will be for sale in the general market, which may mean increased competition in Europe. A further increase of capacity, equaling 2,425,000 tons, is credited to the year 1904, of which 405,000 tons will be thrown on the general market, o that a total of 1,310,000 tons is likely to be thus

THE MODERN TORPEDO.

Commenting during the late Spanish war upon the efficiency of the torpedo, we said: "Although torpedo warfare has not as yet achieved results at all proportionate to the amount of thought and skill that have been devoted to it, the failure has probably been due more to a lack of opportunity or of efficient

handling than to any deficiency in the torpedo itself." The startling events torpedo itself. that marked the opening of the Russo-Japan war have established the truth of that statement, for in the hands of an alert, intelligent, and daring people, this deadly weapon, in the first half hour of hostilities, sank two of the finest battleships and one of the best cruis ers of the Russian navy, and incidentally struck a blow at the naval prestige of Russia from which that country will take many years to recover. At the same time, the Port Arthur torpedo attack must be judged at its true value; and, therefore, we must not lose sight of the fact that information is finding its way to the public ear which makes it pretty evident that the Russian ships were not looking for, and were totally unprepared to receive, a torpedo attack. If this is the case, what has been proved is that if the torpedo boat can get un-molested within easy range, the torpedo is fairly sure of its mark-and this we all knew well enough before the

The Whitehead torpedo is undergoing constant development, the latest improvement being the introduction of the gyroscope for the purpose of keeping the torpedo more accurately upon its true course. The latest patterns include this device and are generally of larger diameter and greater length than the earlier types. We show illustrations of a Schwartzkopff torpedo, which is the type used in the Russian navy. It is merely a modification of the Whitehead and operates upon the same prin-

cipies. In a later issue we shall illustrate the latest type of Whitehead as used in the Japanese navy, and illustrate in detail the operation of the Obrey gyroscope.

The torpedo here shown consists of a cigar-shaped body of phosphor-bronze or steel, divided into six separate compartments as follows: 1, the magazine; 2, the secret chamber; 3, the reservoir; 4, the engine compartment; 5; the buoyancy compartment; 6, the bevel-gear chamber.

The magazine contains the explosive charge, which

pedo strikes the water, the rotation of the little propellers releases the sleeve and leaves the firing pin ready to strike the detonating primer the moment the torpedo meets an obstruction.

The "secret chamber" is the most ingenious part of this most ingenious piece of mechanism. Its piston, pendulum, and springs perform the important work of



Copyright by Frank H. Child.

TORPEDO PRACTICE AT NEWPORT, B. I.-LAUNCHING A WHITEHEAD TOR-PEDO FROM THE TORPEDO-BOAT "MORRIS."

regulating the horizontal rudders which keep the torpedo at the proper depth. Immediately in front of the secret chamber is a narrow compartment perforated on its walls to allow the outside water to enter. The front wall of the secret chamber carries a piston, a, which can move in the direction of the axis of the torpedo. The pressure of the water is resisted by three coiled springs, as shown in the longitudinal section. At a certain predetermined depth, according to the tension on the springs, the springs and water pressure will be in equilibrium; below that depth the piston

first part of its run is made on a wave line which crosses and recrosses the desired and ultimate level of immersion, the piston and the pendulum gradually bringing the torpedo to a true course. The reservoir forms the central body of the "fish." It is made of forged cast steel and is tested up to seventy atmospheres. A tuyere at its after end feeds the air to the engine. The torpedo is driven by a

engine. The torpedo is driven by a three-cylinder engine, with cylinders 120 deg. apart, acting on a common crank. The engine is started by means of a valve which is opened by a lever striking a projecting lug on the launching tube, when the torpedo is fired.

The buoyancy chamber is an air-tight compartment, the purpose of which is to afford the proper buoyancy to the torpedo; it carries a piece of lead ballast, by shifting which the trim can be controlled. The two tubes, f and g, carry the connecting rods for controlling the horizontal diving rudders.

Next comes the bevel gear chamber, where is located the gear, l, for causing the propellers, m, to rotate in opposite directions. The after propeller is keyed to the main shaft; the forward propeller is keyed to a sleeve which rotates freely upon the main shaft, and the motion is reversed by means of two bevel-wheel gears which turn on a spindle at right angles to the main shaft. The "tail" consists of a stock with vertical vanes, which act as the vertical rudder, and two frames which carry the horizontal rudders.

The torpedo is fired from a launching tube by the explosion of a small charge of gunpowder behind it. This compresses the air which surrounds the rear half of the torpedo and thrusts it out of the tube without any serious jar.

The range and speed of the torpedoes vary with the size. The weapon here shown is 14 inches in diameter, 15 feet in length, carries 90 pounds of guncotton, and has a speed of 28 knots for a range of 800 yards. The 18-inch Whitehead torpedo

a range of 800 yards. The 18-inch Whitehead torpedo is 16 feet $7\frac{1}{2}$ inches in length, carries a charge of 220 pounds of guncotton, and has a speed of 31 knots for 1,000 yards.

The Destructive Action of Radium on Fabrics.

In a recent number of Nature Mr. Blythswood states that he happened to replace the usual mica plates used in connection with the ordinary ebonite box with a piece of cambric, so as to permit the whole of the emanations to pass out, the mica storping the alpha




SIDE VIEW OF A 14-INCH TORPEDO.

consists of a series of disks of wet guncotton packed snugly together. The cartridge primer, k, for exploding the charge, consists of several cylinders of dry guacotton packed in a tube which passes through perforations in the guncotton disks, l. The foremost of the six cylinders contains a detonating primer consisting of fulminate of mercury. The small propeller at the extreme point of the torpedo is part of an ingenious safety device for preventing premature explosion in handling. When not in use, the firing pin held in check by a sleeve; but as soon as the tor-

will be driven in by the water pressure, and above it the springs will push forward the piston. To prevent too sudden oscillation in this action, the piston is connected to the rod, e, of a swinging pendulum. d. The motion of the piston is communicated by rods, which pass through the hollow stay rods of the air chamber to the horizontal or diving rudders. If the torpedo goes too deep, the piston moves back, the pendulum swings forward, and the rudders are elevated, the reverse movements taking place if the immersion is not sufficient. When a torpedo dives into the water, the

rays. In four days the cambric was rotted away. Mr. Blythswood states that he has renewed the cambric several times with the same result.

The United States Navy Bureau of Steam Engineering is about to place an order for nickel steel boiler tubes and condenser tubes, to be installed on one of the vessels plying in home waters, so that the tests which will be made can be under constant supervision. A careful comparison will be made of this material and the simple steel tubes now in use.



f. explosive charge; k. careridge primer; a. safety device to check premature explosion; a., depth-regulating platon; c. rod of swinging pendulms d; 4, compressed air chamber; f and g, tubes that contain reds connecting depth-regulating device a. s. d, with diving radders; h, bevel goar for caseing propellers m to rotate in opposite directions; n, vertical radder.

CONGITUDINAL SECTION THROUGH A SCHWARTZKOPFF TORPEDO, A TYPE USED IN THE RUSSIAN NAVY.

Scientific American

JUPITER AND HIS SURFACE CURRENTS.

BY THE REV. T. E. R. PHILLIPS, M.A., F.R.A.S.

The general aspect in the telescope of the planet Jupiter is well known. His markedly elliptical disk, which is distinctly brighter in the center and gradu ally fades off toward the limb, is traversed by a series of dusky belts which vary from time to time both in width and position. These belts frequently show great irregularities at the edges, being broken up or indented by a number of light and dark spots, while dusky wisps are eften to be seen projecting from them across the bright zones which separate them. The accompanying drawings will serve to illustrate the gen eral arrangement of the surface features and also the great and rapid changes of aspect to which they are subject. Thus it will be seen from the illustrations that in the years 1896 and 1898 (Figs. 1 and 3)—as was also the case in 1901 and 1903—the belt lying north of the equator was quite narrow, but that at other times it was broad, and exhibited numerous condensations and white spots at its edges. It not in-frequently happens that the general aspect of the planet undergoes a marked alteration even in the course of a single apparition. Thus Fig. 6 represents view of Jupiter in June, 1902, but by the latter part the autumn the appearance of the disk had materially changed. The equatorial regions were intense ly white-a very striking contrast to the rich, warm,

coppery tone which was so marked a feature of the planet a few years ago—and the whole of the disk morth of the N. temperate belt was deeply shaded with a delicate bluish gray.

it

al

11

is ne it

et

do

tes

ith

Mr.

e of

It prob able that some of the changes on Jupiter are of a cyclical or seasonal character. Mr. Stanley Williams in a valuable paper com municated to the Royal As tronomical Society in April, 1899. showed from a discus sion of a large number of ob servations extending over many years that there remarkable variation in the color of the two prin cipal equatorial belts. Thus, when the equatorial belt is at a maxi-

mum of redness, the N. equatorial belt is at a minimum, or even bluish in tone, and vice versa. The mean period of these variations is found to be about twelve years, and as this corresponds with the length of a sidereal revolution of Jupiter round the sun, it is probable that the change observed is of a seasonal character. The maximum redness occurs soon after the vernal equinox of the particular hemisphere in which the belt exhibiting it is situated. In accordance with the interesting conclusion at which Mr. Williams has arrived, the N. equatorial belt has lately been intensely red, and the S. equatorial belt almost colorless, except in the region immediately following the Red Spot bay.

But, perhaps, the most interesting and instructive feature hitherto observed in connection with Jupiter is the difference of speed with which his spots and other markings are drifting. So long ago as the latter part of the seventeenth century, Cassini found that the markings in the neighborhood of the equator performed a rotation in nearly six minutes less time than was required by objects further north and south. Sir William Herschel, Schröter, and other observers confirmed this result, but as the outcome of the labors of more modern investigators, a considerable number of distinct currents are now known to control the movements of Jupiter's surface material. There can be not be doubt that many recorded changes on Jupiter are

in reality due to the great proper motions of the objects observed, which quickly cause them to become relatively displaced.

With one or two exceptions these surface currents are pretty constant. Their velocity varies within certain limits, and the latitude of their boundaries is not always the same, but whenever definite spots or observable condensations appear their movements of rotation are nearly always found to conform more or less closely to the normal speed of that latitude.


But interesting as is the investigation of these surface currents, the real nature of Jupiter's physical condition is the problem which students of the planet must endeavor to solve. It has generally been agreed that the belts and spots of Jupiter are of the nature of clouds and atmospheric vapors; that the true globe of the planet has never been seen; and that its real rotation period is consequently unknown. But whatever view may be adopted as to the vaporous character or otherwise of the visible features of the disk, it is probable that the internal body of the planet rotates in a period somewhat longer than any markings we can observe—possibly in a period just a minute or so less than 10 hours. As regards the relative altitudes of the various markings, there seems good reason to suppose that the more swiftly moving objects are situated at a greater height than those which move more slowly. Of course, it must be remembered that the

we catch a glimpse, though on a giant scale, of our own world in the dim recesses of the past.—Abstracted from Knowledge.

The Chord Galvanometer and the Human Electrocardiogram.

In the Archives Néerlandaises, W. Binthoven has indicated the principle of a novel galvanometer, made up of a silvered quarts thread, stretched like a chord in a strong magnetic field. As soon as an electric current was led through the thread, the latter will diverge at right angles to the direction of the magnetic flux, the amount of deflection being directly measured by means of a microscope with an eyepiece micrometer. Some important improvements of the instrument have been made, enabling the chord (a quarts thread 2.4 millimeters in thickness and 10,000 ohms in resistance) to be stretched strongly. Under certain circumstances, currents not higher than 10—3 amperes may be detected by the instrument. The chord may be stretched sufficiently to have a current of a given strength produce a predetermined deflection. The image of the middle of the chord, after being magnified 660 times, is thrown on a split perpendicular to the image of the chord. In front of the split there is a cylindric lens, the axis of which is parallel to the split, while behind a photographic plate is moved in the direction of the image of the chord.


time, a system of co-ordinates projected the sensiplate ao cording Garten's meth horizontal m 1111 meter scale, distely sensitive the sharp hado t h e division the 6B plate. ereas th vertical are due to the spokes disk uniformiy in tercepting t e r m lttently the on photo grams thus ob tained it is inforred that the deflections, be aperiod) ortion ensities of the



1896, March, 2d. 6h. 30m. G.M.T.

1897, March, 9d. 11h. 55m. G.M.T.

55m. G.M.T. 1898, April, 44. 9h. 55m. G.M.T.



1899, April, 15d, 12h. 10m, G.M.T.

1900, April, 20d. 14h. 15m. G.M T.

1902, June, 26d. 14h. 31m. G.M.T.

CHANGES IN THE ASPECT OF THE PLANET JUPITER OBSERVED AT VARIOUS TIMES.

planet may have no solid or definite surface divided off from the vapors which form its belts and spots. It is highly probable—bearing in mind the very low density of Jupiter—that the whole globe is still in an intensely heated, semi-molten, and viscous condition, and that what we see is but the outermost shell of visible material. Prof. Hough, in his important and valuable paper already referred to, suggests that the visible boundary of Jupiter has a density of about one-half that of water, is of the nature of a liquid, and that in it are immersed the Red Spot and others whose motion in longitude and latitude are slow and gradual, and which are tolerably permanent or long enduring. He considers that the equatorial and other belts may be at the surface of this liquid or at a higher level than the Red Spot, and that the equatorial regions may be concealed by overlying vapors at a much greater altitude, in which openings and irregular condensations give rise to the appearance of white and dark spots.

No doubt there are many interesting questions in connection with Jupiter of which the solution must be left for future students; but this much, at any rate, we may suggest with some confidence: We look at Mars and our own satellite; in them we see a forecast of physical conditions to which some day the earth must at least approximately attain. We look at Jupiter, and, in the constant agitation of his heated globe,

current. This instrument is applied by the author to determining the human electrocardiogram discovered by A. D. Waller (Philoso. Transactions, vol. 180, 1899, B. p. 169). It is interesting to note the constancy in the form of this curve for a given person, the alterations occurring in the course of time being so small as to allow with little practice to recognise many persons by their electrocardiograms.

Russia and Korea's Non-Participation in the St. Louis Fair.

The American Ambassador at St. Petersburg has cabled to the State Department at Washington that the Russian government has notified him of its intention to withdraw from participation in the St. Louis Fair.

A similar notice of withdrawal has been sent by

To prevent further disasters, such as that which visited Galveston, Tex., in 1900, when 3,000 houses were destroyed and 8,000 lives were lost in the floods, it is proposed to raise the whole of the city. According to the present plan, earth is to be brought from along the coasts of the Gulf and banked upon the site of the city, so that it shall be at level of from 17 feet to 20 feet above the sea.



Protected Cruiser "Askeld."
4,500 tons. 30 knots.
Hole below waterline.

Protected Cruiser "Variag."
6,800 tone. 26.6 knote.
Sunk by gun fire.

Protected Cruiser "Rovik." 2,000 tons. 38 knots. Hole below waterline.

Protected Cruiser "Pallada."


A#80 tons. 30 knots.

Gunbost "Korietz."

1,00 tons. 11 knots.

Bunk by run fire.

RUSSIAN BATTLESHIPS AND CRUISERS DISABLED



Battleship "Retvizan." 12,700 tons. 18.6 knots. Sunk by torpedo.

Battleship "Poltava." 11,000 tons. 17 knots. Hole below waterline.

Protected Cruiser "Boyarin." 8,900 tons. 20.5 knots. Sunk by mine.

Protected Cruiser "Diana."
4,600 tons. 20 knots.
Hole below waterline.
[See page 2004]

Sunk by torpedo.

Torpedo Transport "Yenesel."

2,500 tons. 18 knots.
Sunk by mine.

By The Japanese in the first week of the war.

RUSSIA'S LOSSES IN THE FIRST WEEK OF THE WAR.

There has been no war of modern times in which there was such a dearth of reliable information as in the present struggle between Russia and Japan. If we carefully sift out all the sensational reports with which the papers have been flooded, we find that the only really reliable information is contained in the brief but expressive official reports sent by Admiral Alexieff, the Russian Viceroy in the Far East, to the Czar. These, supplemented by a few authentic accounts by eye-witnesses and some meager information from the Japanese government, enable us to tabulate the number of Russian ships that have been disabled, but without being able to state, except in two cases, what is the nature and extent of their injuries.

It has been proved in the case of ships of our own navy that it takes but a mere touch of a reef of sand or rock to send a ship to the drydock for several at a stretch; yet, speaking broadly, it may said that injuries from striking a reef are relatively pared with the blowing in of a large section of the ship's side or bottom, which must result from n of a modern Whitehead torpedo ing over 200 pounds of guncotton. Consequently, may be safely assumed that the Russian ships which have been disabled by torpedoes are put out of action. at least for several weeks, probably for several m and quite possibly, for good. Of the eleven Russian vessels already disabled in the war, we know that three, the battleships "Czarevitch," of 13,000 tons, and "Retvizan," of 12,700 tons, and the cruiser "Pallada of 6,630 tons, were disabled by the torpedo during the first attack on Port Arthur. We think it is unlikely that either of the two battleships can be made available for active service except, perhaps, in a more of crippled condition, during the present war, and this for the following reasons: The draft of these vessels at normal displacement is 26 feet, and since they were probably in war trim, with a full comple-ment of sea stores and coal aboard, the draft may easily have been 28 feet. The crushing in of the bottom or side by the torpedo must have resulted in the flooding of at least one compartment, if not two would easily add another three feet or more to the draft, especially if the vessels had taken on a heavy list, throwing one bilge deeper in the water Now, the Port Arthur dock is supposed to be only about 450 feet in length, and it is quite possible that it has only a draft of 28 feet over the sill, in which case the disabled battleships would be unable to enter unless the bottom could be temporarily patched up made sufficiently air-tight to permit of pumping out the damaged compartments. This presumption is borne out by a recent report supposed to emanate from Arthur, to the effect that these two ships are to be employed as guard ships at Port Arthur, until some opportunity occurs to send them for repairs to the big drydock at Vladivostok. The cruiser "Pallada," of 6,630 tons, whose draft is only 21 feet, will probably take her turn in drydock, that is if she is still affect. In addition to these three vessels, that are known to be seriously crippled, two others, the protected cruiser "Boyarin," of 3,200 tons, and the torpedo transport "Yenesel," of 2,500 tons, have been oist with their own petard," by coming in contact with submarine mines that had been laid for the protection of Port Arthur harbor. These two vessels may be stricken off the list for good. Two other ships, the cruiser "Variag," of 6,500 tons, and the gunboat "Kori ets," of 1,500 tons, were sunk by gun fire at the battle of Chemulpho. If they are floated it will be by the Japanese salvage ships, and they will become an asset of their navy. The battleship "Poltova." of 11,000 tons, and the cruisers "Pallada," "Askold," and "Diana," vessels of about 6,500 tons and 23 knots speed, are reported as having been disabled by a neath the waterline," the same description being used of the injury to the 3,000-ton protected cruised "Novik." It is puzzling to determine just what this injury amounts to, or by what agency it was inflicted. If the ships were penetrated by gun fire, the holes would scarcely be below the waterline, unless the vesrel happened to be rolling her under-body out of the water at the time the shell struck. It is, of course, possible that the hole was made by some solid projectile that struck the ship with a plunging effect hitting her just at the waterline on the side that was exposed to fire, and passing out below the waterline on the other side. If the injury were not caused by a shell, it must have been the work of the torpedo, in which case these vessels must be included in the terrible list of fatalities wrought by the Japanese destroyers. There is presumptive evidence that the cruisers were injured by gun fire, in the fact that the "Novik" is reported as having left the dock after repairs were made, for it is certain that no injury wrought by a torpedo could be made good in so short a time.

After one has taken the most optimistic view p

After one has taken the most optimistic view possible of the present condition of the Russian fleet, the fact remains that in the very first week of the war. a fleet of eleven vessels, all but one of which were of the most modern and approved construction, and several of which were among the very best of their class, were temporarily or permanently disabled, and four at least of them completely lost to the Russian navy. If one wishes to obtain a vivid idea of the enormous damage entailed in this one week of the war, he has but to look at our double-page illustration, showing this fleet of eleven ships assembled in one group, and then turn to the accompanying table, showing the size and

BUSSIAN SHIPS LOST OR DISABLED IN FIRST FEW DAYS OF THE

Name.	Date.	Tons.	Cost.	Nature of Damage.
Czareviteh	1901	18,000	\$6,900,000	Torpedoed.
Retvizan	1900	12,700	6.500,000	Torpedoed,
Poltova 1	1894	11,000	5,500,000	Hole below waterline
Pallada	1809	6,630	3,000,000	Torpedoed,
Askold	1900	6,500	3,000,000	Hulled at waterline.
Diana	1809	6,630	3,000,000	Hulled at waterline.
Varing	1900	6,500	3,000,000	Sunk by gun fire.
Boyarin	1900	8,200	1,400,000	Blown up by mine.
Novik	1900	3,000	1,300,000	Hulled at waterline.
Korietz	1886	1,500	450,000	Sunk by gun fire.
Yenesei	1900	2,500	800,000	Blown up by mine.
Founage and value of ships destroyed or				
disabled		73,160	\$34,850,000	

cost of each vessel. Here we have eleven ships of a total tonnage of 73,160 tons, and a total cost of about \$35,000,000, put out of action at a cost in torpedoes, powder, and shell to the Japanese of far less than the cost of the "Korietz," the smallest vessel in the disabled fleet.

Such is modern naval warfare. It was believed that it would be swift, sudden, disastrous, and costly. The first seven days of this, the first struggle between two navies that were both well equipped and thoroughly up-to-date, has proved that modern naval warfare is even more terrific than was foretoid.

Melting Out Frozen Water Pipes Electrically.

During the recent intense weather the method of thawing out frozen water pipes electrically was undertaken successfully at Altoona, Pa. Mr. E. B. Greene, the well-known superintendent of the Edison Electric Illuminating Company of that city. He now writes to the Electrical World and Engineer as follows concerning practical results:

We use for this purpose alternating current of low voltage, the maximum voltage not being over 50. The method of doing this, as you know, originated with Messrs. Jackson and Wood about the year 1900, so you will appreciate that it is not new with us. We use a 25-kilowatt transformer wound for 50 volts, using an amperemeter to know what quantity of current we are using, and reduce the voltage with a water rheostat, using common table salt to impart the necessary conductivity.

The transformer, water rheostat, and instruments are assembled in a box which is hauled out to the place desired to use, when the transformer is connected up to run as in ordinary methods of lighting, using the water rheostat on the primary side of the transformer (as this requires a very much smaller vessel for the water rheostat). The secondary, or low-voltage cables, are connected directly to the spigot or to the pipe inside the building, the other one being connected to a fire plug, or, if more convenient, to the pipe in the adjoining house, which then completes the circuit on the Iron pipe for the low potential.

We have thawed 250 feet of one-inch pipe in twenty

We have thawed 250 feet of one-inch pipe in twenty minutes actual time of current on, using between 18 and 20 kilowatts. In smaller services, say % inch, and on 30 or 40 feet, we have thawed out in from five to eight minutes, using about 11 to 15 kilowatts. The apparatus is very small and it is quite a convenience to people to have water, when their pipes are frozen, in two or three hours after asking to have the apparatus connected up. There is, of course, very little business in the sale of current in connection with the above, but the advertisement we get from being able to help out people who don't have water we think will repay us amply for the trouble and the expense entailed.

As you, no doubt, can see from the above the cost of sending out the transformer, the time of the men connecting up and disconnecting, and the draying charges would leave very small margin unless you would charge an excessive price, which we don't believe it pays us to do. The cost varies very much. The cheapest job, which was near by the station, was \$2.50; the most expensive one was \$9.50; yet the amount of current used is a very small amount as compared with the charges for labor and drayage.

Electrical Notes.

The news comes from Paris that the operation of extracting radium from the ores has been considerably shortened. The preliminary process, which reduces the material to laboratory dimensions, now occupies one month, whereas it has previously taken three months. It is estimated that up to the present about 730 tons of ore have been used to produce about one-fifth of an ounce of radium.

Advices from Canada state that the Canadian government is looking into the subject of the electrical smeiting of iron, and is sending a commissioner to Europe to study the subject. Canada has many valuable iron ore deposits in the vicinity of large water powers which could be utilized for generating a cheap supply of electrical energy.

What is known as the inverted arc lamp, and which has been used for illumination in some workshops for many years, is suggested for the artificial lighting of lawn tennis courts on dull days and at evening time. An installation of these lamps has recently been put up at the tennis courts at Sheen, near Richmond, and was brought into use recently at a special tournament arranged to test the capabilities of the light. Four lamps of 1,500 candle power each are arranged around the court, an even illumination being obtained with the aid of screen sheets, from which the light is reflected. The experiment is said to have been a success, the illumination obtained being only slightly inferior to daylight on bright days.—Electrical Eng. (London).

It has been frequently found by experimenters that when an oxide of a metal, whose temperatures of reduction and volatilization are nearly the same, is mixed with sufficient cerbon to combine with the oxygen, and heated to the temperature of reduction, the main resulting product is not the metal which is wanted, but a carbide. The reason is thought to be that the metal becomes volatile as soon as it is formed and combines with free carbon present in the mixture. In patent granted to Mr. F. J. Tone, engineer of the Carborundum Company, of Niagara Falls, and de-scribed in the Electrical World, these disadvantages are overcome by maintaining proper conditions of tem perature, proper distribution of heat, and proper arrangements of the charge. The method may be de scribed by its application to the production of silicon for a mixture of silica and carbon. The constituents finally subdivided and thoroughly design of the furnace is such that the discharge of heat is over a wide zone (as opposed to localized heat), so that the progress of the reaction is relatively slow and the best conditions are maintained for agglomerating the particles. The most even tempera-ture possible is maintained throughout the zone of reaction, to prevent the silicon from being volatilized as soon as formed, and the charge is so arranged in the furnace as to allow globules of reduced silicon to drop by gravity out of the zone of reaction to a lower portion of the furnace. It is evident that for these purposes an arc furnace would be unsuitable. Mr. Tone therefore employs a resistance furnace. The heating resistance in the center of the furnace is made up of carbon blocks piled together with intervening The charge is fed into the furnace at the top and as the silicon is reduced it sinks down into the cooler portion of the furnace, and finally into the re-ceptacles at the bottom, where it solidifies as a metallie block.

The Current Supplement.

The opening article of the current Supplement, No. 1470, deals with the whale-oil industry of the United States. It is copiously illustrated. Various types of rails used in Europe and in America are described in an exhaustive article. Dugald C. Jackson's paper on the typical college course dealing with the professional and theoretical phases of electrical engineering is published in full. Foreign and American types of horizontal boring machines electrically operated are described by F. C. Perkins. Dr. Samuel G. Tracy writes instructively on thorium and its therapeutical possibilities. Kretschmer's tetrahedral design for boats is described in full. "Tobogganing in a Basket" is the title of an entertaining article by Laura B. Starr. The usual notes will be found in the Supplement.

The Depth of the Antarctic Ocean.

The State Department has received from John Barrett, United States Minister to the Argentine Republic, a communication to the effect that the Scotia scientific expedition, sent to the Antarctic from Scotland to make meteorological and oceanographical observations, cruised about five thousand miles to the south and east of the South Orkney Islands, between longitude 16 degrees west and 45 degrees west and as far south as 70 degrees 25 minutes, and in this region located a deep sea of an almost uniform depth of 2,500 fathoms. The deepest sounding was 2,739 fathoms, or 16,434 feet.

201

THE "SCOOTER."

That "necessity is the mother of invention" finds singular and forcible illustration in the ice-scooter, which, essentially a Long Island creation, is almost as necessary there in the winter as are the yachts in

the summer season. It is an amphibious craft, combining in its construction a modification of both the yacht and ice boat, the advantages of each of which it possesses in a remarkable degree.


Reference to the illustrations will show both the sail arrangement and runners on the bottom. It is to these latter, perhaps, that the speed and steady flight of the ice-scooter is due, as well as to the absence of a rudder, which would necessarily arrest the free motion. The jib is utilized for a rudder, serving the double purpose of directing the course and tacking. Steel runners are said to be preferable to those of brass, through their superior hardness, which prevents any sliding when a tack is being made. Such an amphibious boat will lay within five points of the wind, and can execute, in less time and space, any evolution which an ice boat or yacht can perform. Incredible speed is attained by the larger and more completely equipped scooters, and when their respective courses run parallel, they can often maintain their lead over a fast express train. While a boy can manage one of these strange craft, the requirements and possibilities are such as

to afford exhibitanting sport for a strong man in handling the sails and obtaining the maximum degree of speed possible under given conditions.

The sail area is always determined by the capacity

The sail area is always determined by the capacity for carrying canvas on the ice. When the water is reached there is consequently, under normal wind conditions, a dangerous excess of sail, and the utmost skill is required to avert an accident. Such is the proficiency attained by the votaries of "scootering," however, that injury to the owners or scooters is rarely if ever witnessed.

There are, perhaps, few more interesting sights seen



SQUARE-END SCOW FITTED UP AS A "SCOOTER,"

than those afforded by a scooter plunging at full speed from the ice into the water. At such times the water, cleaved as by a shot hurled from a cannon, is thrown into the air a distance of twenty feet, completely enshrouding the scooter from view until, with speed little diminished, it glides smoothly and triumphantly out upon the ice at the other side of the opening.

While "scootering" provides a healthy and hearten-


ing sport for the South Beach life savers during their long period of enforced leisure, its value consists chiefly in permitting them to cross to their mainland homes over thin and treacherous ice when no other means would permit of such visits. It also affords an

> easy and speedy access to vessels caught in the ice when intervening open-water patches or unsafe ice would render the tendering of assistance impossible.

> Long Island sportsmen have also adopted the craft, and successfully employ it in carrying them to favorite duck and goose hunting grounds on the ice, miles away from the shore. When the point for shooting operations is reached, the sail can be furled and the mast removed. Then, by covering the scooter with cakes of ice or snow, it provides an ideal concealed shelter from which to shoot birds.

The scooter has been suggested as a more sure, safe, and speedy method of reaching the North Poie than any hither to devised. It can be carried on the vessel as far as open water will admit, and, after it has been loaded with provisions, the journey can be continued with it, as neither ice nor water presents any obstacles to its progress. While, like the summer yacht, these boats may be built with any degree of elaborateness, those used on Long Island are made with a view to speed and lightness rather than to other objects.

One of our illustrations also shows a square-end scow fitted up as a scooter. This boat is a home-made affair, and, to be properly steered, requires the use of a rudder. The rudder, it will be observed, consists of a metal blade secured to a pole in such a manner that when in water it can be used as an oar blade, and when out of the water its edge will cut into the ice, thus affording a suitable means for steering the boat.



FLEET OF "SCOOTERS" AT GREAT SOUTH BAY, LONG ISLAND.



OVERTURNED "SCOOTER," SHOWING THE STEEL RUNNERS ON THE BOTTOM.

RECENTLY PATENTED INVENTIONS.

Electrical Bevices.
ELECTRIC SWITCH.—W. K. Dodon, Man-titan, Kan. The invention is in the nature battan, Kan. of a switch so constructed and arranged that two or more lights or sets of lights or any combination of the same may be thrown into circuit and the circuits which are "on" are plainly indicated from the exterior of the case. It committees in the novel construction and argement of the switch and in the combination h the same of an indicator which plainly ws what circuits are turned on even in the

Engineering Improvements.

Ragineering improvements.

BTEAM-BOILER.—N. I. Wansen, Macon, Gg. An object in this case is to provide a belier of large heating capacity, but requiring comparatively little floor-space and so arranged that it may be readily inspected and cleaned both within and without. Space between the tubes will permit a person to inspect flues and other parts of the interior, and the boiler is provided with a manhole, normally closed by a cover.

TRACK-SANDER FOR LOCOMOTIVES .-G. M. Schwend, Birmingham, Ala. The inten-tion in this improvement is to utilize water as a medium for effecting the discharge of sand from the reservoir or sand-box usually arranged upon the boiler of the locomotive, the same being delivered upon the rails in front of or behind the driving-wheels for understood pur-poses. The apparatus is gradulty coind the driving wheels for understood pur-noses. The apparatus is specially adapted for using and is any condition—that is, wet or ry sand—as it may be had from banks thereof t any point along the track.

at any point along the track,

LOCOMOTIVE-VALVE.—H. G. CONYKLI and

J. E. STEPRINA, Marietta, Ga. The present invention has for its object the provision of a
valve designed to be operated from the outer
ide of the locomotive and by means of which
the steam may be quickly cut off from either
one of the steam-chests should accident or
breakage occur in one of the chests, thus permitting the locomotive to be at once worked
from the opposite or intact steam-chest.

Miscellaneous.

PIPE.—E. Skapper, Seattle, Wash. The improvement is particularly in pipes for use in carrying sand, gravel, and other material from dredges, hydraulics, or other excavating devices, the pipe being particularly designed for use as a dredger delivery-pipe. Pipes used for carrying the above samed material are rapidly worn out by the grinding of the same as it passes through. The wooden lining of blocks on end, with the hoops to hold the blocks in place, is designed for the lining of any pipe, the object being to increase the life of pipes where the west is great enough to wear them out in a few months.

COLLAR OR CUFF HOLDER.—E. L. PITTS, COLLAR OR CUFF HOLDER.—E. L. PITTS, Jerome, Arksoan Ter. This device holds cuffs and holds coliars in place when in use. In use the device may be buttoned by a divided button to the neckband, or to the wristband, and a socketed head be forced through the buttonhole of the collar or cuff, as the case may be, and a hinged section be then adjusted over the collar or cuff and a spring-catch be forced to the property of the collar or cuff and a spring-catch be forced to the sections become covered to the culture of the culture of the culture of the cut of the the socketed head to secure the collar or

Cuff as dealted.

VAEVE.—N. OBOLENBRU, Hermitage, N. Y.
The object of this case is to provide a vaive,
arranged to allow of regulating the speed of
the water or other fluid passing through the
vaive to prevent leakage and to give convenient access to the parts for repairs and
for quick replacement of worn-out parts and
for other purposes. The invention refers to
check-vaives, such as shown and described in
Letters Patent formerely granted to this inven-Letters Patent formerly granted to this inven-

DRAWERS-SUPPORTER.-H. W. ew York, N. Y. The purpose in this in DRAWERS-SUPPORTER.—H. W. Post, sew York, N. Y. The purpose in this instance is to provide a form of supporter adapted for stachment at the inner portion of the waist-and of the trousers, the supporter constructed, referably, of one piece of wire of suitable age of a strip of metal of any cross-sectional hape, the supporter comprising two loops glidly held apart and means whereby the defice may be secured to the inner face of the relational or between the layers forming the ame projecting upwarf at the inner face of the trousers-waistband.

PIRE-EXTINGUISHER. L.-P. Yost, Wee-Mr. Yost's invention FIRE-EXTINGUISHER.—F. Your, Wee-hawken Heights, N. J. Mr. Yout'n invention pertains particularly to improvements in port-able hand-operated extinguishers of the class designed to contain an extinguishing chemical solution, an object being to provide clamping devices of novel form and operation for tightly bolding the pump mechanism in place; and another object is to provide a piston-rod with a large air capacity, the confined air acting as a piston.

ING TROUSERS.—F. STRVENA, STRUCTURE, N. Y. The aim in view in this case is the provision of a curable article adapted for the purpose of stretching trousers to take out the "bagging" in the knees thereof or for pressing the trousers, to the end that the wrinkles and bagging may be removed and made to present a peat appearance.

NG AND CARRYING DEVICE.-M.

plication of this invention is to a holsting de-vice for lifting the cylinders of cotton-seed linters from their bearings and conveying the cylinders to a desired point. The principal object is to provide a device for hoisting the duiled cylinder from its bearings and remov-ing the same to a suitable point, after which a sharpened cylinder may be conveyed by the holsting mechanism to the linter and substi-tuted for the previous cylinder. TILE—8. B. FLINT, New York, N. Y. The

TILE.—8. B. FLINT, New York, N. Y. The tiles are of such construction that they may be assembled by hooking together, to the end that each tile assists in holding a series of that each tile assists in holding a series of other tiles in piace, and in a manner to pre-vent separation, notwithstanding that they are subjected to strain in any direction. The tile has considerable strength owing to the dis-position of the recesses and the construction of the hooking projections. Their correspond-ing shape and size enable them to be assem-bled easily and quickly for covering a surface of any size

of any size.

TWINE-HOLDER.—R. A. STEER, Roselle, N. J. The object of the invention is to provide a twine-holder, more especially designed fo household use in conveniently storing od pieces of twine, cord, string, thread, and thike, such as are received from stores, etc. arranged to permit of winding up in a spoo and tied together to allow ready use of the continuous twine thus formed for tying pack ages, bundles, boxes, etc. The holder mains be used for holding a ball of twine, etc. if not too large for the device, one end of the spool being removable permitting the ball to be placed on the spool.

FLY-CATCHER.—J. ZIERL, Hechingen, Ger

be placed on the spool.

FLY-CATCHER.—J. Zheal, Hechingen, Germany. In this patent the invention is embodied in a body or bar provided at the top with a receiver or holder for the tacky substance and at the lower end with a reservoir for the flies, also with detachable end portions which are adapted to receive the tacky substance and to be interchanged when the lower one becomes full.

stance and to be interchanged when the lower one becomes full.

MUSICAL INSTRUMENT.—E. S. STEVENSON, Eldorado, Kan. The purpose in this case is to provide an instrument having the general characteristics of a guitar—that is, as to its strings and notes, with an auxiliary set of strings and frets with stops by means of which a large number of notes and variations of scales may be quickly made with a small number of the auxiliary strings.

MEANS FOR ATTACHING STIRRUP-LEATHERS TO RIDING-SAIDILES.—J. MANTIN. Chalet Elisabeth, Avenue des Casernes, Grasse, France. The aim of the present invention is to construct a support for stirrupleathers in which when the rider falls from his horse and his foot remains in the stirrup the stirrup-leather becomes detached from the saddle by the weight of the rider. When in the saddle the rider may bear upon the stirrup without fear.* rups without fear.

rups without fear."

HORRE-COLLAR.—J. V. STONE, Moorhead, Minn. This invention has reference to improvements in horse-collars, and the object is to construct a collar having a stuffed body and pneumatic pad which will serve to protect the horse's shoulder. Should the bag collapse, the driver need not unblich, since the stuffing forms a body of the usual shape, and a horse could pull as well with both bags collapsed as with an ordinary hard collar.

with an ordinary hard collar.

DESIGN FOR A COVER-DISH.—R. L.
JOHNSON, Hanley, Stafford, England. The
plan of the cover-dish shows a symmetrical
oval shape. The outline of the side presentation is beautifully curved from the handle of
the cover down to the flanged base. The handles at the ends are very gracefully fashioned.
The ornamental decorations are richly spread
around and near the edge of the cover, the The ornamental decorations are richly spread around and near the edge of the cover, the upper part of the body, and the base.

upper part of the body, and the base.

AUTOMATIC OR SELF-ACTING GATE.—

J. DELAUNAY and R. VASQUER, Buenos Ayres,
Argentina. The gate may be opened from
either side by pulling a cord and in every case
the gate opens away from the passer. The
opening is effected by moving to one side or
the other the upper end of the rod or axie on
which the gate is hinged, whereupon the gate
under action of gravity swings open in the
direction in which its axis has been inclined.

RECEIVER FOR MAIL, ETC.—N. D. CLEAR-

RECEIVER FOR MAIL, ETC.—N. D. CLEAR-WATER, Binghamton, N. T. The device consists of a box hinged to the Jam of an outer door of a residence. The box is open only at one side through which packages may be placed in or removed from the box. When a package is placed in the box, the box may be swung on its hinges until the open side lies against the door of the house. In this position it is held by a spring latch which can be released only through the open side of the box. The contents of the box are thus rendered secure against theft, for they cannot be removed except by opening the door of the bouse. RECEIVER FOR MAIL, ETC.-N. D. CLEAR

CLOTHES-DRIER. - P. S. MacDougall, eattle, Washington. This clothes drier co oted to a rotatable carrier which a leaf hinged to a back-board. on a sear integration a necessaria. When its time the leaf is awing to a horisontal position at right angles to the back-board and is held by a latch. Means are provided for holding the rotatable carrier in any desired position.

Norm.—Copies of any of these patents will be furnished by Munn & Oo, for ten cents each. Please state the name of the patenties, iffile of the invention, and date of this paper.

Business and Personal Wants.

READ THIS COLUMN CAREFULLY,—You will find inquiries for certain classes of articles numbered in consecutive order. If you manufacture these goods write us at once and we will send you the name and address of the party desiring the information. In every case it is necessary to give the number of the inquiry. MUNN &

Marine Iron Works. Chicago. Catalogue free

Inquiry No. 5183.—For makers of pyrometer uitable for regulating the heat of a tin-plating bath. AUTOS.—Duryea Power Co., Reading, Pa.

Inquiry No. 3184.—For parties engaged in pr
ag premium magazines.

For hoisting engines. J. S. Mundy, Newark, N. J.

Inquiry No. 5185.—For manufacturers of silver ware, watches and clocks, dinner sets, dishes, etc. C. S." Metal Polish. Indianapolis. Samples free.

Inquiry No. 5186. For makers of paper carto uch as are used for cysters, ice cream, etc. Handle & Spoke Mchy. Ober Mfg. Co., 10 Bell St.

Inquiry No. 5187.-For makers of electric automatic knitting machines.

Sawmill machinery and outfits manufactured by the ane Mfg. Co., Box 13, Montpeller, Vt.

Inquiry No. 5188.—For makers of refrigerating plants, abattoirs, air compressors, boilers, steam engines, ventilators, pumps, hydraulic presses, etc.

FOR SALE.—Patent right on newly invented propel er. B. Charles, 25 So. 14th St., Newark, N. J. Inquiry No. 5189. For machinery for preparing

FF Send for new and complete catalogue of S and other Books for sale by Munn & Co., 361 Bi New York. Free on application

Inquiry No. 5190.—For machinery for the preparation of tinned meat

The largest manufacturer in the world of merry-go-counds, shooting galleries and hand organs. For prices and terms write to C. W. Parker, Abliene, Kan. Inquiry No. 5191.—For machinery for making

nns.
The celebrated "Horneby-Akroyd" Patent Safety Oil
Engine is built by the De La Vergne Refrigerating Mahine Company. Foot of East 18th Street, New York.

Inquiry No. 5192, For machinery for mechanical workshop, such as carpenters' utensis for iron and brass foundry, metallic roofs, filtration systems, pipes cranes, rails, tracks, cars, etc., also all materials, implements and accessories connected with this industry

Manufacturers of patent articles, dies, metal stamp-ing, acrew machine work, hardware specialties, machin-ery and tools. Quadriga Manufacturing Company, 18 South Canal Street, Chicago.

Inquiry No. 5193.—For makers of ice-harvesting nachines, for cutting and for filling houses.

WANTED.—An up-to-date superintendent for our lant employing 20 men; foundry, machine shop and rood shop. Also foreman for machine shop, and fore-lant for wood shop. DeLouch Mill Manufacturing ompany, Atlanta, Ga.

I squiry No. 5194.—For makers of lathe maching for making all kinds of turnings, such as druggists' sees. etc.

wanted. Hevolutionary Documents, Autograph Let-ers, Journals, Prints, Washington Portraits, Early knerican Illustrated Magnatines, Early Patents signed by Presidents of the United States. Valentine's fanuals of the early 60%. Correspondence solicited. Address C. A. M., Box 753, New York.

Inquiry No. 5193.—For makers of ice-making sachinery, such as plants of from four to ten ton capa-Inquiry No. 5196.—For manufacturers of molding machines for molding wax cakes.

Inquiry No. 5197.—For manufacturers of light older bearings, suitable for grindstone shafts and edal shafts.

Inquiry No. 5188, -For machinery for erecting a

Inquiry No. 5199.—For makers of oulley blocks for clotheslines, also for makers of clothes dryers, such as used in kitchen.

Inquiry No. 5300.—For the address of the manufacturer of the Magic Flute.

Inquiry No. 5201.—For the manufacturer of a small check punch having stamped thereon the following: "Grabler's Patent, Jan. 7, 1902, U. S. A."

Inquiry No. 5262.—For makers of the quarters of a hollow sphere, to be made in sheet metal in sizes 8, 12, 16, 20 and 24 inches diameter of sphere. Inquiry No. 5203.—For parties engaged in form-ng or bending spring wire.

Inquiry No. 5964.-For makers of small tanks ande of copper and galvanised from.

Inquiry No. 5205 .- For manufacturers of chain

Inquiry No. 5306. - For manufacturers of boots.

Inquiry No. 5207, -For machinery for cutting

Inquiry No. 3268.—For makers of Tripoli stone, uch as used in filters.

Inquiry No. 5209, -For parties to make small

Inquiry No. 5210, For makers of small steel bains the size of watch chains.

Inquiry No. 3211.—For small castings for boat againes and motors, of 2 to 5 h, p.

Inquiry No. 5313,-For makers of metal and cloth button machinery.

Inquiry No. 5213.-For makers of carronsels or riding galleries.

Inquiry No. 5214.-For an outfit of archery Inquiry No. 3215.—For makers of small articles uitable for canvassing.

Inquiry No. 5216.—For manufacturers of card subjecting and card beveling machines.

Inquiry No. 5217.-For manufacturers of pnou-

Inquiry No. 5218. -For makers of gas engine costleasiry No. 5219.—For makers of headless steel hat pins.

Inquiry No. 5220. For makers of castings of creen of castings of

Inquiry No. 5221.—For the maker of a machine for producing quartered figures on plain oak lumber. Inquiry No. 5222. For makers of gasoline or hot air engines of about 14 h. p.



HINTS TO CORRESPONDENTS.

HINTS TO CORRESPONDENTS.

Names and Address must accompany all letters or
no attention will be paid thereto. This is for
our information and not for publication.

Beferences to former articles or answers should give
date of paper and page or number of question.

Inquiries not answersed in reasonable time should be
repeated; correspondents will bear in mind that
some answers require not a little research, and,
though we endeavor to reply to all either by
letter or in this department, each must take
his turn.

wishing to purchase any article not adver-ed in our columns will be furnished with ireases of houses manufacturing or carrying

addresses of houses manufacturing or carrying the same, cical Written Information on matters of personal rather than general interest cannot be expected without remuneration, entific American Supplements referred to may be had at the office. Price 10 cents each, Books referred to promptly supplied on receipt of

erals sent for examination should be distinctly marked or labeled.

(9324) W. I. R. says: Can you give (9324) W. I. R. says: Can you give be through the inquiry column of the Scientific American, a reliable formula for determining the number of square feet needed for team or bot water radiators? A. The amount f radiating surface for steam heating varies considerably with the variable exposure of sooms. For bouse heating with low-pressure team, in rooms with much exposure and rooms. For house heating with low-pressure and windows on two sides of the room, a good rule is one square foot of radiating surface for each eighty cubic feet of room space, and for bedrooms of small exposure, one square foot steam surface to 120 cubic feet is a good rule. For halls and reception rooms, 1 to 100 is the general rule. For hot-water heating about 15 per cent larger than above surface should be supplied.

(9325) V. R. W. asks: Kindly inform me through your Notes and Queries whether or not molten lead when orpped in small quan-tities from a receptacle, from a great height, will form into spherical shapes while passing through space. A. Small quantities of moiten lead when dropped from such a height that it will solidify before reaching the earth will be found to be in the shape of spheres. It is in this way that shot is manufactured. All drops of liquids are in the form of spheres,

NEW BOOKS, ETC.

MACHINE DESIGN

MACHINE DESIGN.

We have received from the American School of Correspondence, Chicago, a copy of their new instruction paper on Machine Design. This paper has been prepared by Mr. Charles L. Griffin, who was formerly Professor of Machine Design at Pennsylvania State College, and has since had ample opportunity to put theory into practice, as chief draftsman of a prominent manufacturing company at Syracuse, N. Y. The results of his experience are clearly shown in the instruction paper. Mr. Griffin approaches his subject methodically. In fact, "method" is the key word of the whole paper, and characterizes its whole teaching. The student is first clearly taught the meaning of machine design and its relation to the problems it has to solve, viewed from the point of theory, and then from the point of production. With the relative and mutual importance of these points clearly in mind, the method of design is next taken up. The student is shown the importance of a complete analysis of the problem—its conditions and forces—before undertaking its solution. Then he must attack the problem incentically, sketching out his design on scientific lines. he must attack the problem theoretically, sketching out his design on scientific lines. The theoretical design when completed must The theoretical design when completed must be modified to suit practical requirements. Not until these steps have been successively fol-lowed out can the delineation and specification be taken up. These steps are clearly illus-trated by a practical example, and the student is instructed to pursue them in every proble attacked, until they become so familiar as be intuitively applied. Delineation and spefication are just as methodically taught, the student is thoroughly grounded in important principles before taking up-tions of mechanical construction and a ment. The importance of such a method attacking a problem will appeal to every perfenced designer. In these days "syst attacking a problem will appeal to every experienced designer. In these days "system" plays a very important part in the success of business enterprises, and particularly in manufacturing concerns. It is a simple task to teach a new draftsman the "system" of one's drafting room, but quite a different matter to teach him a good system of thinking, a correct method of dealing with all questions which confront him, a "mechanical sense" which may be depended upon to result in scientific designing. It is a difficult matter to induce the draftsman to break away scientific designing. It is a dimension away to induce the draftsman to break away from his habit of guessing at proportions and dimensions without knowing their exact purpose or meaning. The time for learning a proper system of mechanical thought should, and the beginning of the state of the system of the beginning of the sality. Inquiry No. 5223.—For a small hand loom for waving rac carpsta and looms.

Inquiry No. 5223.—For a small hand loom for waving rac carpsta and looms.

Inquiry No. 5224.—For a device for cleaning disterns of the shape of a common wooden backet.

Inquiry No. 5225.—For and evice for cleaning disterns of the shape of a common wooden backet.

Inquiry No. 5225.—For an amall hand loom for wave looks and the shape of a common wooden backet.

Inquiry No. 5225.—For a small hand loom for wave looks and the shape of a small hand loom for wave looks and looms. We are pleased to find that the American School of Correspondence appreciates the importance of system in thought, and has given it due emphasis at the outset fans for vestilating purposes.



Star" Star" Foot and Power Cutting Cross Lathes

FOR FINE, ACCURATE WORK Send for Catalogue B.
SENECA FALLS MFG. CO.
698 Water Street,
Seneca Falls, N. Y., U. S. A.

ATHES SEBASTIAN LATHE CO

SCHIEREN BELTING

Is the product of long experience, the best Packer bides, the purset oak bark that grows, and a tannery that knows none but the most modern methods. Schieren Belt ting is reasonable in price and highly satis-factory in service. grows, and a tanner; the most modern methods. Schieren benting is reasonable in price and highly satisfactory in service.

Send for our Dixie Belt Leather Booklet.

CHAS. A. SCHIEREN & CO.

NEW YORK: 50 Ferry St.

CHERAGO 19 Franklin St.

Borron: 192 Lincoln St.

HAMBURD DESVER: 1819 Statesonk St.

Pitkhabet & Pit

Veeder

o register reciprocating novements or revolu-ions. Cut full size,





THE CLIPPER CLIP 18 Its triangular shape prevents entangling and gives three times the capacity of any other Clip for attaching papers together. Best & Cheapest. Ail Stationers.

CLIPPER MFG. CO., 401 West 124th St., New York, U.S.A.

A BIG SAVING in GAS

CARTER" ACETYLENE GAS it generates from carbide and water, producing a better light of highest candle power. Purer, safer, cleaner, than ordinary gas. Takes up little room. Saves much money

NIAGARA FALLS ACETYLENE GAS GENERATOR CO., Niagara Falls, N.Y.



A Constant Water Supply Without Cost of Maintenance

is best afforded by the use of a NIAGARA HYDRAULIC RAM The Niagara is a new improvement upon ngara Hydraulic Engine Co., Chester, Pa.

INDUCTION COILS for experiments in X rays and other electrical work.

1 E. S. RITCHIE & SONS BROOKLINE, MASS

NO LOOP-HOLES

If guarantee, for it makes every body safe.—"Horse, if the Beltiable Insubator docum'r give esticate hatches after a fair test." Askrahout it and get our annual catalogue free. Just send 10c, to pay postage, lable iscubsiter and Brader Ca., Bar B-195, Quincy, Hi.



Lackawanna Reversing Device



need to the term t


ex-m" of

to te's

se" in ter

Within the boundary of reversing devices "The Lackawanna" rules saprenea. Used in connection the same services are supported to be the same services and the same services are supported to reversing gear. Simple and reliable. Price \$15.00 met. LACKAWANNA MOTOR CO.

51-61 Letchworth St., Buffnie, N. Y.



INDEX OF INVENTIONS

For which Letters Patent of the United States were Issued for the Week Ending

February 23, 1904.


AND EACH BEARING THAT DATE

Acid comnounds, making organic, W. Baumi 702,047
Acid, making sulphuric, Heins & Hegeler. 702,677
Acids, making organic, N. Zelinsky 782,744
Air brake operating device, G. J. Berbert. 782,743
Air brake operating device, G. J. Berbert. 782,744
Air prake operating device, G. J. Berbert. 782,744
Air brake operating device, G. J. Berbert. 782,744
Air brake operating device, G. J. Berbert. 782,745
Air Breadana. W. Manney. 782,745
Air manney. Polythase magneto, L. J. Le Pontois. 782,691
Alternator, polythase magneto, L. J. Le Pontois. 782,692
Aluminum sulphate, preparing, H. F. De Schwahn
Anusement device, W. C. Parsells. 782,692
Anusement device, W. C. Parsells. 782,692
Anusement device, W. C. Parsells. 782,693
Anusemble receiver. H. G. Pape. 782,795
Automobile circulating system, H. C. Osborn Azie lubricator, car, J. R. Fleming. 782,897
Azie mechanism, driving, R. H. White. 782,898
Bale the, H. De Haven. 782,898
Basket making machine, O. Schleicher, research of the run it issue
Basket making machine, O. Schleicher, research of the run it issue
Balt tub, U, A. Ricks. 783,092

Basket making machine, O. Schleicher, re-issue
Bath tub, C. A. Ricks.
Bed apring device, swinging, H. D. Smith.
Bedstead, camp, H. R. Wykert
Belt, F. Hey!.
Bevel and square, J. Graff.
Bin. See Storage bin.
Binder cover, A. Hertje.
Binder, loose leaf, E. T. A. Akass.
Block signal system, electric, C. W. S. Turner



FINISHING FLOORS





Nothing but Kerosone Oil to run li

Simple, Sate and Efficient. Needs it attention, is less likely to get out order, and is cheaper to run than i other corine manufactured. Economical cal and Easily Operated. ternational Power Vehicle Co. Stamford, Conn.

WIRE UP Properly and you will save trouble. We send you a box assorted wire and cable terminals with full instructions for 68c. postpaid. Special ignition cable and wires. Write HERZ & CO. 55 Grand Street New York





THE MIETZ & WEISS KEROSENE

To 40 H. P.
Send for
Canadague.

Canad

THE



H. C. MacRAE



"The truth. whole truth nothing but the the truth" in time telling means the time as told by the

ELGIN

Every Elgin Watch is fully guaranteed. All jew have Elgin Watches. "Timernakers and Timekeepers, illustrated history of the watch, sent free upon required histo

READY APRIL 15. Spangenberg's Steam and

Electrical Engineering
By E. SPANGENBERG, M. E.
former Superintendent of the fit. Louis School of Engineering.
Containing 1,666 Questions and Answers, with 668 Illustrations. Price. \$3.46.
The best book on the subject ever published.
GEO. A. ZELLER, Publisher, Enab. 1870
68 S. Fourth St. St. Louis, Mo.



FOR LIGHT AND MEDIUM WORK B. F. BARNES

Upright Drill is the best tool made.

Substantial, well built up to date. The
diving power is strong and positive—the
will drill from t. 16-men to N-inch.
Beadinch matter on request.

S. F. BARNES COMPANY, Reckford, Ill.

BABBITT METALS,—SIX IMPORTANT formulas. SCIENTIFIC AMERICAN SUPPLEMENT 1123. Price Doents. For sale by Mund & Co. and all news. dealers. Send for catalogue.

BASOLINE ENGINE

Simple. Economical, Durable. Suitable for all kinds of work,

BACKUS WATER MOTOR, cheapest power known.

BACKUS WATER MOTOR CO., Newark, N.J., U.S.A.

DRILLING

or 70 sites and styles, for drilling either deep or ow wells in any find of soil or rock. Mounted needs or on sills. With sections of horse powers, simple and durable. Any mechanic cate them easily, Send for catalog.

WILLIAM BROSS, Ithaon, N. V.



The Highest Efficiency

is guaranteed in every one of the smooth-raming
Brennan Casoline Motors
made on the latest approved pattern, safe, sure and quick of earl, commical in fact, and of great durability. Can be used for Marino purposes.

BRENAN MFG. CO.
BREASCOR, N. Y., U.S.A.



The Best Dry Battery " SPARKING

Beeko Spark Cell

J. H. BUNNELL & CO.

JEFFREY ELEVATING--CONVEYING--POWER THE JEFFREY MFG. CO.
Transmission-Screening--Dredging--Coal Cutting Drilling--Mauling--Washing Machinery.

DRAWING

Mechanical Electrical

Sanitary

TELEPHONY

TAUGHT BY CORRESPONDENCE

Illustrated bulletin giving full information free on request.



UNDREDS of aspiring young and middle-aged men in all walks of life know what the instruction of the American School of Correspondence is. Other hundreds need just such instruction to enable them to get on in life. To bring to the attention of draftsmen, engineers, architects, drawing teachers and others interested in drawing, the high standard of our instruction, we have compiled from the regular instruction papers in our Drawing Courses a practical treatise under the title of

Compendium of Drawing

ONE THOUSAND ILLUSTRATIONS ns, diagrams and folding plates

TWO VOLUMES Y Y 900 PAGES

00 OR TWO MONTHLY PAYMENTS OF \$3 EACH SINGLE VOLUMES \$3 EACH

By Express Prepaid. Money Refunded if Not Satisfactory

On receipt of the price (Address Room 124k) and the names of two persons whom you know to be interested in our courses (designating the course), the books will be sent, express prepaid. If the work is not all we claim, return it in 10 days and get your

Money back.

A compendium of such practical value and covering so many branches of drawing has never before been offered. The separate volumes necessary to cover the ground would easily cost \$15.00.

We offer the work practically at cost, believing that it will be the means of interesting you further in the work of the School.

> AUTHORS OF TREATISES IN THE WORK. PART II.
> PROP. W. H. JAMES,
> Massachusetts Institute of Technology.

MINE OF PAGE 7x10 inc.

PULLY

PROP. E. KENISON,
Massachusetts Institute of Technology,
PROP. H. W. GARDNER,
Massachusetts Institute of Technology,
PROP. D. A. GREGG,
Massachusetts Institute of Technology,
PROP. W. H. LAWRENCE,
Massachusetts Institute of Technology,
P. C. BROWN. P. C. BROWN, Architect, Boston

PROF. C. I., GRIFFIN, Pennsylvania State Formerly College, WM. NEUBECKER, New York Trade School,

PARTIAL TABLE OF CONTENTS
PART I. PART II.

MECHANICAL DRAWING

SHADES AND SHADOWS PEN AND INK RENDERING

Accents, Faults, Ren-PERSPECTIVE DRAWING

ciples, Station Point, Vanishing its, Ground Line, Horison Line, of sures, Perspective Plan, One Point spective, Curves, Distortion. ARCHITECTURAL LETTERING

dy of Old Examples, Forms, Propor-as, Composition, Spacing, Full Fage amples, Greek, Roman, Gothic, Re-mance, Office Lettering.

WORKING DRAWINGS AND MECHANISM

Threads, Bolts, Nuts, Scale and Assembly Drawings, Blue Printing, Cams, Pulleys, Belts, Gearing, Pencil Layouts, Working Drawings, Cost, Dimensions, Lettering, Order Sheets.

MACHINE DESIGN

Theoretical and Commercial Considera-tions, Original Design, Handbooks, Data, Calculations, Notes, Records, Porces, Stresses, Power Transmission, Speed Radio, Power, Lond, Layout, Pelts, Pul-leys, Shafts, Gears, Clutches.

SHEET METAL PATTERN DRAFTING AND TINSMITHING

Construction, Tools, Intersections, Developments, Irregular Shapes, Triangulation. Approximate Developments, Practical Shop Problems.

The regular examination questions of the School are bound

into each volume to test the reader's knowledge.

This is merely a synopsis of the contents, but it will serve to convey an idea of the thoroughness of the instruction, the character of the men who prepare the instruction and the value of the instruction to every young man who enrolls in the School. In each of our 60 different courses the character of the instruction is equally authoritative, equally thorough and equally valuable to the student.

AMERICAN SCHOOL OF CORRESPONDENCE

ARMOUR INSTITUTE OF TECHNOLOGY

E. M. Miller
sik for hotel registers, G. P. Rose, Jr.
sinfecting device, F. A. Martin.
sor, gate, or like hanger, Rohde & Hastlings
sor, gate, or like hanger, Rohde & Hastlings
sor, gate, or like hanger, Rohde &
Hastsings
sor, J. J.
weel, J. Gusowski
art equalizer, F. R. Goode
aft equalizer, F. R. Goode
aft equalizer, J. Farmer
awing tool, combination, P. Neukirchen
sedge, O. K. Hogan.
ter, See Grain drier,
ying apparatus for wool, etc., Kelth &
Hiller pring apparatus for wool, etc. Kelth & Drilling and boring machines, bed fastening for horisontal spindle, G. H. Smith. Driving mechanism, J. F. Kay Donat pan, W. H. Hills.

Dyrstuffs, G. Howland.

Esterical illuminating device for show windows. J. H. Goehst

Electrical riceptacle. P. H. Fielding.

Elevator safety appn. M. Hanford.

Smbosdier of Abric, A. Eurgess.

Sond gate, J. W. Schirmer.

Ey Songhes Sparking apparatus, explosive, L. H. Fey Songhes Sparking apparatus, explosive, L. H. For Songhes Sparking apparatus, explosive, L. H. For Songhes Sparking apparatus, explosive, L. H. Songhes Sparking apparatus, explosive descriptions apparatus, e Enu gas-Engline sparking apparatus, explosite. 1752,832 Engline tender, traction, W. S. Kelley. 752,684 Englines, cooling attachment for internal combustion, J. W. Sutton. 753,013 Englines, producing sparks in the cylinders of internal combustion, L. J. Le Dontois 752,600 Exewating, raising, screening, and filling gravel ballast, etc., machine for, H. 753,702 avating, raising, screening, and filling gravel ballast, etc., machine for, H. Quertier , oscillating with the property of the ace, W. B.
ace grate, H. A. Poppon, C. Kert
o. See Saw table gage.
c. J. J. Butterworth
nent supporting menns, C. W. Mesick,
engine, A. G. Bonan.
from wells, obtaining, A. S. Cooper,
generator, acetylene, A. E. Schileder,
generator, acetylene, H. W. Koehler,
beater, H. A. Schmidt
seulator, automatic, F. W. Priestley, Gas generator, acetylene, A. E. Schlieder. 752, 795
Gas partentor, acetylene, H. W. Koehler. 752, 985
Gas regulator, automatic. F. W. Priestley, et al. Gas regulator, et al. Hair pins, apparatus for making, D. H.
Haiyard, E. A. Ashiand.
Hammer, claw, E. A. Ashiand.
Hanger, G. Nissenson.
Hay and stock rack, J. H. Anderson.
Heating water by steam, apparatus for, W.
Heating water by steam, apparatus for, W.
Heinet, J. J. Curtis.
Hinge, gate, C. Pelmider.
Holsting mechanism, safety and signaling device for, W. N. Dickinson, Jr. or apHolsting mechanism, safety and signaling device for, W. N. Dickinson, Jr. or apHospe to cancer.
Hospe to cancer.
Hospe to the form of 752,650 753,152 752,890 752,900 752,928 753,081 753,161 753,133 752,787 anitting machine bur wheel support, R. W. Gormly
Knitting machine cloth wheel or cloth shoe,
T. F. Holloran,
Knockalan St. Rehn
Knockalan St. Rehn
Knockalan St. Rehn
Labels, wrappers, ric, machine for applying, C. W. Cheney, reinsue
Lamp, R. P. Habel.
Lamp, C. G. Holmberg.
Lamp burner, J. Gregory
Lamp burner, Gunnell & O'Toole
Lamp, clietric arc, Schußfer & Bergmann
Lamp, portable electric, H. C. Hubbell.
Level, plumb, J. J. Lankford.
Level, plumb, J. J. Lankford. 752,666 12,197 753,066 753,075 752,901 753,065



Commends itself to travelers by land or sea, on account of its convenience, compactness, luxury and economy.

THE J. B. WILLIAMS CO., Gla

Valuable Books! Home Mechanics for Amateurs

By GEORGE M. HOPKINS
Author of "Experimental Science"

326 Engravings Price \$1.50

370 Pages

THIS important work has achieved great popularity. It tells how to do things. The New York Tribune says: "The book may be commended for its practicability and suggestiveness and will be found to appeal to boy readers almost as much as to older amateur mechanics."

CONTENTS

Woodworking
How to Make Household Ornaments
Metal Working
Model Engines and Boilers
Meteorology
Telescopes and Microscopes
Electricity

Each subject is adequately treated.

Send for free descriptive circular.

The Scientific American

Cycloped a Notes and 3

15,000 Receipts. 734 Pages.

Price, 85.00 in Cloth. 86.00 in Sheep. 86.50
in Half Morecce. Post Free.



This work has been 900 New Formulas,

The work is on arranged as to be of use not only to the specialist, but to the general reader. It should have a p lace in every bonne and workshop, the special reader of Contents will be sent on application. Those who already have the Cyclopedia may obtain the

1901 APPENDIX.

TWENTY-THIRD EDITION EXPERIMENTAL SCIENCE.

By GEORGE 71. HOPKINS

sized and Greatly Enlarged. 2 Octago Volume.

Pages. 800 Historations. Cloth Brunch, Postpa

\$4.00. Half Morocco, Pustpaid, \$45.00 or

Volume; Half Morocco,

\$4.00 per Volume; Half Morocco,

\$4.00 per Volume.

EXPERIMENTAL SCIENCE is so well known of our readers that it is hardly necessary



752,865 753,138 753,149

752,654 752,656

753,115

palaiel

ag jack, F. V. Dalton.

Bee Skylight.

ing ring, A. J. Black

d, apparatus for delive

uantities of, H. J. S. (

active corine

753,054
799 upon application
753,012
MUNN & CO., 361 Broadway, New York



Intrinsic Merit is in Morgan & Wright Clincher

Nothing has been omitted, nothing overdone, in naking it a tire that can be depended apen. In it is tough, strong, resilient, serviceable. It minimizes tire troubles and enhances the pleas-re of automobiling. The most critical investigation is courted.

nd for a copy of "A Tree Triumph," which treats of the tire

MORGAN @ WRIGHT 22 May Street Chicago

The 1904 Haynes

S

1.50

vork great tells The

ular.

ints, nd ?

6.50

en re-

ulas.

angred
nly to
to the
hould
every
p. A
full
s will
m.
have

1X.

CE.

wn to how to on of opkins aonths id be pare a swork many yveries might d in its lished, yvelop s tee-ample, e. It theredeal of uld be ork in the thoreto, and in view have years and in the thoreto, and in the thoreto, and in the thoreto, it has olivides

N



TUBULAR DRIVING LAMP. IT is the only perfect one. IT gives a clear, while light. IT gives a clear, while light. IT throws the light straight light. IT throws the light straight. IT burns kerosene. Send for book (free). R. E. DIETZ CO., 60 Laight Street, New York.

N. E. DIETZ CO., 60 Laight Street, New York. Mention this paper and get special discount. —ESTABLISHED 1840.

HE NICKEL PLATE ROAD AGAIN SELLS ING LOW RATE COLONIST TICKETS TO THE PACIFIC COAST.

Tickots on sale every day. March t to April ®, strate of \$42.50. These tickets are good in our trans-continental tourist eleopers and via any route desired beyond chicago. For full particulars see local agents, or write R. R. Payne, General Agent 29. Main Street, Buthin, N. Y., or A. W. Ecclestone, D. P. A., 855 Broadway, New York.



Send For It To-Day

bave as a useful and instructive book Montgomery & Co.'s Tool Catalogue The new edition has 70t pages and is coptionally illustrated. Pocket size 64x 64 ins. Sent by mail for 25c.

MONTGOMERY & COLY.

106 Fulton 8t., New York City.



Paper folding machine, Nind & Strasburger

Paper reel, J. & F. H. Hoberg. 752,965

Paper reel, J. & F. H. Hoberg. 752,857

Paper reinmer, W. H. Keeling. 752,845

Pedial, G. Merritt. 752,946

Pel stretcher, F. M. Bowman. 752,966

Pen and penedl hobber and calendar, combustion, H. J. Mellon. 753,988

Penedl, conving. E. Markovita. 752,857

Penedl, conving. E. Markovita. 753,087

Penedl sharpener and point protector, W. A. Tew

Photograph table, A. A. TONNEAU, \$3,550 compete. \$2,450 without top and front glass. TWO-PASSNAGER TOURING CAR. Penell sharpener and point protector, W. A. 752,935 Penell sharpener and point protect Plate handling machine, E. Miles, 752,915 to 752,915 Platen, adjustable, G. W. Donning. 753,190 Plag, attachment, P. H. Fielding. 752,835 Policeman's mace, P. O. Evensen. 752,835 Polity of Printing machine, sectional wheel for, J. H. Fogarty. 752,936 Power transmission. Sectional wheel for, Printing and folding machine, W. Scott. 753,135 Printing machine, multicolor, 500, 500 Printing machine, multicolor, 500, 500 Printing machine, ticket, F. C. Osborn. 752,2540 Printing machine, when the printing machine, ticket, F. C. Osborn. 752,2540 Printing on tins, I. Kitsee. 753,1640 Printing printing machine, who W. Spalchaver. 752,866 Police printing machine, who W. Spalchaver. 752,866 Police printing machine, ticket, F. C. Osborn. 752,2540 Printing prachine, producing duplicate, F. & A. Leelle. 753,061 Printing press, J. A. Gates. 753,061 Printing of time. It Albert Printing plates, producing duplicate, F. & A. Leatle Total Review of the Printing press, J. A. Gates 753, 964
Printing press, J. Lowe 1753, 964
Printing press, J. Lowe 1753, 967
Protractor, H. Woodbloom, 753, 975
Pulley, clutch, W. J. Hilliard 753, 973
Pulley, clutch, W. J. Hilliard 753, 973
Pulley for threshing machines, paper cylinder, O. Berg 1753, 973
Pulp press, woad, B. E. Boschert 753, 958
Pump, beer, J. Grunfinger 752, 968
Pump, centrifugal, L. Lowe 1753, 154
Pump for switching mechanisms, electric, W. J. Bell 752, 952
W. J. Bell 752, 953
Pumps, clectrical apparatus for registering the discharge of liquids by H. J. 8, 752, 852
Pumplag apparatus, J. E. Smith 752, 715

the discharge of liquids by, H. J. 8.

Cassal

Pumping apparatus. J. E. Smith. 752,715

Radiator, G. M. Aylawerd. 752,715

Radiator, Da water, J. J. Lawler. 752,877

Radiator, Da water, J. J. Lawler. 752,887

Radiator, Da water, J. J. Lawler. 752,887

Radiator, Da water, J. J. Lawler. 752,887

Radiator, Da water, J. J. Lawler. 752,877

Raliway, W. Lay. 753,157

Raliway brake head and shoe therefor, C. W. Armbrust. 752,877

Raliway switch, J. T. Evans. 752,673

Raliway switch, J. T. Evans. 752,718

Raliway switch, J. R. Smith. Chandler. 752,718

Raliway switch, J. R. Switch. 752,718

Raliway switch, J. R. Switch. 752,718

Raliway switch, J. R. Switch. 752,718

Raliway te, J. G. Shuster. 753,171

Raliway track laying apparatus, G. F. H.

Elicks. 752,682





752, 846 One Dollar. GARTON-DANIELS CO. 753, 061 754, 164 752, 679 755, 023 758, 073



The "Best"

The World's Best Light Sold in every civilized coun-try on earth. Costs less than kerosene, given oil times inore light than electricity. A Pure White Steady Light akes and burns its own gas, a wick, no odor, no smoke, acolutely safe. For indoor d sation, up.

Agenta Wanted, Exclusive territory, illoral commissions. Catalog free. THE BEST LIGHT CO. 87 & 50 St. CANTON, GHID.

Twenty-Third Edition

SCIENCE George M. Hopkins

Revised and Greatly Enlarged. 2 Octavo Volumes.

1,100 Pages. 900 Illustrations. Cloth Bound, Postpaid, \$5.00. Half Morocco, Postpaid, 7.00. Or Volumes Sold Separately; Cloth, \$3.00 per Volume. Half Morocco, \$4.00 per Volume.





Steel Castings for Special Purposes

Our complete facilities enable us to undertake the manufacture of high goods used custings for almost day purpose. Write us for particulars, these Hearth Stood Castings for Inventures, also besiding, election, pump and general machinery purposes. Subject to U. S. Government, Lieptin, Stationed and other specifications. Hait. on Warm DELYREMEN.

HEABOARD STEEL CASTING CO., Chester, Pa.

RADIUM

John B. Rogers & Co.

THE SPINTHARISCOPE With particle of Radium, postpaid, \$9.60.
Williams, REGWN & EARLE.
Sept. 6 Fis Chestaut St., Philadelphia, Pa.



A MOTOR CYCLE SMALL COST by soing one of or nebable Motor Occits. Thorough tites. Also complete Motor Cycle stags, etc. Beyele, automobile, m LOWHET PRICES. Soud stam STEFFET MPG. CO.

ELECTRIC SEWING MACHINE MOfor. The inserged; we are numerous illustrations of de-ails contained in his article will coulse any nechanic of average ability to build an emission to make the large process a serving durchine. The cost of make the large trape of the large trape and the large trape of the large trape of the large trape and the large trape of the second by mal, from this office and from all newsdealers.

INDIAN MOTOCYCLE



HENDEE MFG. CO. SPRINGFIELD, MASS.



BARKER MOTORS

C. L. Barker, Norwelk, Ct.



ding a sketch and description may talk our opinion free whather a revoluty patentable. Communica-condidental. Handbook on Patent deet areany fur securing patents, can through MUNN' & CO. receive, without charge, in the

Scientific American handsomely illustrated weekly. Largest cir-lation of any scientific journal. Terms, \$5 as ar: four mouths, \$1. Sold by all newschealers. MUNN & CO. 361 Broadway. NewYork



KENT POCKET METERS

Automatic Vell-Ammeter is desugned and on-lorated especially and the succession of t

Presses for Sub-Press Work.

Five sizes. Sub-Presses and Tools to order.

JUHNSON, WATERBURY, CONN. BLAKE & JOHNSON,



METAL POLISHES.—FORMULAS FOR Puts Poundes, Pastes, Liquids, Powders and doops, for polishing metals, are contained in SCIENTIFIC AMERI-CAN SUPPLEMENT NOS. 1:1833, 1288 and 12898. Price 19 cents asoch from this office and all nuwdealers

NO CUESSING ABOUT IT. You put my Caliper over your work and you know in an anstant just what size it is and how much

netant just what size it is and how much too small or too large. Send for Catalogue and Special Discount to ERNST G. SMITH, COLUMBIA, PA

You Drink Down Disease



Berkefeld Filter because it is so scientifically constructed as to suppress every atom of solid matter in the water, thoroughly purifying it Will give one gallon of pure water in

No trouble to clean or keep in order. BERKEFELD FILTER GO., 4 Cedar Street, New York

HERS
INOUBATORS
in more and healther chicks then
your causey habe. Use hose did
at by 36 Generations Representation
from 17 years and the page.
wheater Ob. Sufficient, N. Y.
REVOURSEY
LOOGO, NEW YORK OF BEASIME.



and up, to not your need ofther as to she or price.
Write us, we will interest you,
The Carroll-Januesen Machine Tuel Co.
Batavia, Onto, U. S. A.

For All Sorts of Houses NOTHING equals Patton's Sun-Proof Paints for houses. They protect, preserve and beautify. The experiences of owners, builders, architects and sainters, exercishes prove the value and economy.

PATTON'S **SUN-PROOF PAINTS**

They are meintifically combined, exactly proportioned and accurately mixed by special himory. They outline may push white hast paint and are positively may and weather-proof, and the property of the propert

inble gage, C. A. Norlin..... weighing, J. M. Triner. driver, G. E. Wood. driver, H. S. Pullman. meter. De Lancey & Smith... cleaning apparatus, cotton, Str. 752,872 on, M. W. Faherty.....nt apparatus, W. H. Gileeenw amusement apparatus, W. H. Gil-man and the communication of the c 752,738 Fescades
Fes onlog and twisting apparatus, H. L. Cumnock uning machine, L. Dugauquier uning machine roll cleaning device, V. Maheu

Spinning machine roll cleaning device, V. Maheu
Spoke cutting machine, G. F. Autry 752,969
Spoke cutting machine, G. F. Autry 752,969
Spoke cutting machine, G. F. Autry 752,065
Spring construction, M. D. Kilmer 753,065
Spring construction, M. D. Kilmer 752,763
Stamp, hand, F. Hardy 752,771
Stamp mill launders, separating hopper for, W. O. Nell 762,771
Stamp mill launders, separating hopper for, T62,702
Stamp more proper for the shafts or 752,702
Stamp mortar, multiple, W. A. Merralls 752,903
Stamb lose Reading stand.
Steam boiler, C. E. Chapman 753,041
Steam boiler, C. E. Chapman 752,804
Steam generator H. E. Penney 507,285
Steam generators or the like, heating burner for, R. H. White
Stem winding and setting mechanism, H. 752,846
C. King 752,841 Steam generators of the like, heating burner for, R. H. White
for, R. H. White
Steam generators or the like, heating burner for, R. H. White
Stem winding and setting mechanism, H.
C. King
Storage bih, J. A. Jamieson
Tö.2,641
Store ventilator attachment, C. Felmulder. 73,194
Store ventilator attachment, C. Felmulder. 73,194
Sturpe critiator attachment, C. Felmulder. 73,194
Supporting frame or trellis. A. Corts. 73,194
Surfacing and jointing machine, Burkhardt
& Streich
Switchboard and felmulger. 752,722
Switchboard system, multiple, W. M.
Davis
Switch operating mechanism, multiple, W.
J. Bell
Teaching singing, apparatus for, A. Gusinde 752,894
Telephone attachment, G. B. Buchanan . 752,642
Telephone attachment, G. B. Buchanan . 752,642
Telephone selecting device, W. B. Watkins, 752,923
Telephone selecting device, W. B. Watkins, 753,183
Telephone selecting device, W. B. Watkins, 753,183
Telephone systems, means for synchronining
the instruments of, H. Redmon, et al. 752,710
Temperature regulating apparatus, A. M.
Goodwin . 752,708
Thill coupling, C. S. Lehman . 753,047
Thread bodding and cutting attachment for \$25,895
Thill coupling, C. B. Lehman . 753,052
Thill coupling, C. B. Lehman . 753,052
The selecting machine, C. Bankey . 753,052
Tile, R. McCarrel . 752,007
Tile, Hluminating, J. Jacobs . 753,072

Thread holding and cutting attacument ror spools, D. C. Laird attachment ror spools, D. C. Laird and rotation of the property of the property

752,801 753,168 752,737 753,182 752,799 752,946 753,033

ransparent, Indestruct d Knives. Your own to, Name and Address hand-forged, rasorsteet blad You can represent us. Not mary. Frud at once for catal Co., 1244 W. 10th st., Canton, C 64 6



Now Ready Bound Volume

OF THE

SCIENTIFIC **AMERICAN** BUILDING MONTHLY

VOLUME No. 36 July to December, 1903

A Monthly Magazine of Domestic Architecture Sumptuously Illustrated

272 Illustrations 6 Covers in Tint 132 Pages

Price of Semi-Annual Volume \$2.00 by mail

SPECIAL FEATURES

The Garden at Georgian Court:
Mr. George J. Gould's residence at Lakewood, N. J.

Harber Hill: The Clarence H. Mackay Estate at Rosiyn, L. I. Mr. Karl Bitter on the Sculpture for the St. Louis Exposition.

"The Orchard":
The Country Seat of Mr. James Lawrence Breeze, at Southampton, L. I.

ELECTRICAL ENGINEERING TAUGHT BY MAIL

44 CAN I BECOME AN ELECTRICAL ENGINEER ? " Institute indersed by Thos. A. Edison and others. ELECTRICAL ENGINEER INSTITUTE, 240-248 W. 224 St. New York.

won't answer all purposes. Some are soft, some hard, some medium, some thick, some thin - which shall I use?

Dixon's Pencil Guide, a 32-page book, Indexed by vocations, correctly indicates the right pencil for your use. Sent free.

Department W, JOSEPH DIXON CRUCIBLE CO. Jersey City, N. J.

RADIUM AND THE RADIO-ACTIVE Substances. No better or clearer scientific account bas been published than that contained in SCHENTIFIC AMERICAN SCIPLEMENT 1429. The paper presents all that is at present known about radium and the radio-active substances. Price 80 cents, by mail. Munn & Co., 38 Broadway, New York City and all newsdealers.

What Is Daus' Tip-Top?



copies from pole-written and developing from type-written original, we will also complete from type-written original, we will also complete daplicator, cap nice, without deposits, on ten of the day of the day

The Felix F. Dans Duplicator Co., Dans Bldg , 111 John St., New York

AN ENGINEER'S LIBRARY. HANDBOOK ON ENGINEERING.

HANDROOK ON ENGINEER KING.
By Henry C. Tullay.

Third edition, enlarged and revised, 5000 copies, now read to the copies of the

is devoted to the interest of draftsmen every class and of special value to stud

MONTHLY PAPER 10 cents a Copy \$1.00 per Year

107 The Beckman Building

THE INTERNAL WORK OF THE Wind. By S. F. LARGLEY. A painstaking discussion by the leading author on A crofurmics, of a subject of value to all interested in similar. SCIENTIFIC AMERICAN SUPPLEMENTS 946 and 947. Price in cents each, by mail. Munn & Company, 361 Broadway, New York City, and all newsloslers.



e optically perfect. ester, N. Y.



COSTS 25 CENTS

LASTS 25 YEARS for 85c. Money back if you want it. Manicu.
"A Handy Hand Book of the Hands."
to instruction on the cure of the hands and sall

556 Clinton Ave. S., Roche

DESIGNS.

TRADE MARKS.

Farbenfabriken of Elberfeld 42,140

Antipyretic, Farhenfabriken of Elberfeld
Co.
Antiseptic powder for certain named diseases, D. W. Rees
Ball, base, C. Disch
Beverages having toulc, appetising, and
attimulating properties, compounded, L.
D. Gardner
Boots and shoes, leather, G. Leal.
Boots and shoes, leather, G. Leal.
Bread, biscuits, and cakes made of dried
bananas and cereals, W. A. Jones.
Candy, Murbach Company of Baltimore
City candy, Murbach Company of Baltimore City
Candy klases, Wilder & Buchanan.
Carlis, playing, C. C. Meriwether
Coffee, artificial or substitute, Javril Co.
Cream, evaporated, Van Camp Condensed
Milk Co.
Trading Sheeting, and Jeans, American
Trading Co.
External applications, certain named, Dr.
A. C. Daniels (Incorporated).
Flour, wheat, Washburn, Crosby Co.
Flour, wheat, Thornton & Chester Milling
G. Co. of lubricant in solid form, H. D.
Smith
Gom, chewing, Frank H. Flourier, Markey Plats

Flour, wheat, Thornton & Chester Milling
Co. Grease or lubricant in solid form. H. D.
Hats, men's, Lie Hand and Co.
Hats, waring Hat Manufacturing Co.
Hats, men's, L. Kline & Co.
Heart stimulants, diuretics, and eliminants,
Cor-Ago Co.
Heart stimulants, diuretics, and eliminants,
Cor-Ago Co.
Heart stimulants, diuretics, and eliminants,
Cor-Ago Co.
L. Blakker
Forward Co.
L. Blakker
Knives, pocket, Hockaday Hardware Co.
Lamps and their parts, acetylene, Britelite
Lamp Co.
Medicial preparation for cure of certain
named diseases, Bremner Extract Co.
Medicine, certain named, Molier & Linsett.
Medicine, certain named, Pincele Medicine
Grease or treatment, Pincele Medicine
Tea Co.
Medicine for relief of indigestion, Garfield
Tea Co.
Medicines for treatment of diseases of cats,
C. I. Bickum
Metal scouring and polishing powder, certain
named. Abrasine Co.
More Grease of the Co.
Grease of

42,107 42,143 42,148 42,150

O. Moyer
Perfumes in liquid and powdered form. E.
Palmer
Palmer
Razors, C. F. Ern. Hack 42,143
Razors, C. F. Ern. 42,148
Razors, C. F. Ern. 42,153
Remedies for treatment of certain named discases, George H. White, Incorporated Ropes, cords twine discases 42,125
Ropes, cords twine discase 42,125
Ralve and ontiments of witch hazel or hamalender and the state of the sta

LABELS.

LABELIS.

"Aunt Rhody's Liniment," for liniment,
M. B. Reynolds.
"Day's Violet Enamel," for a lotion, W.
"Epi," for medicine, W. E. Martin & Son.
"Eptelene," for eye medicine, H. C. Wise.
"Galvin's Cough Syrup," for cough syrup,
W. M. Steever
"Holstein Brand," for butter, Illinois
Creamery Co.
"J. L. Howes Balm," for medicine, J. L.
Howes
"J. L. Howes Balm," for medicine, J. L.
Howes 10,776 10,775 10,773 10,768 10,774 10,765 Howes

"J. L. Howes' Magic Relief," for medicine,
J. L. Howes

"J. L. Howes' Remedy," for medicine, J. L.
Howes 10,771 10,772 "J. L. Howes' Remedy," for medicine, J. L. Howes' Nemedite, for medicine W. B. Davis. "L'Union Fait La Force," for hats, Crescent Hat Co. "Parsifal Rye," for whisky, A. A. Wolf & Co. "Poindexter's Tonic," for medicine, A. A. Poindexter's Tonic," for medicine, A. A. Trobilin. "La Control of the Control of 10.763 10,766 10,777

PRINTS.

903

A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1863, will be furnished from this office for 10 cents, provided the name and number of the patent desired and the date be given. Address Munn & Co., 361 Broadway, New

PERFORATED METALS FOR ALL USES. MADE AS REQUIRED.
HARRINGTON & KING PERFORATING & CHICAGO.



The Franklin Model Shop.

Experimental work for inventors anylating in metal from a single piece to a complete working model. Apparatus for congress. Exhibition models, introduce.

We own a patented day tion samples of patented articles, cial tools for making metal novelti inventions perfected. Drawings and signs worked out from inventors' ide Send for circular 9.

PARSELLA & WEED,
129-13 West Sixt Street, New York.

MODELS I CHICAGO MODEL WORK BUILDERS of Special Machinery.



DIES, TOOLS, MODELS and Special Machi Fry. Metal Specialties and Stampings manufactured. HOEFT & MOORE, 85-87 Fifth Ave., Chicago.



42,122 42,101

43,112

42,134

42,116

42,136 42,151

42,155 42,132

42,131

42,120

42,137

42,146


42,102 42,144

42,093

STIMULATION without IRRITATION atore a normal growth where per axist. The Cap is used about ten twice a day and its effects are pleas the sure beginning. We will ref EVANS VACUUM CAP CO.



GAS ENGINE DETAILS.-A VALUA ble and fully illustrated article on this subject is con-tained in SUPPLEMENT No. 1282. Price 10 cents. For sale by Munn & Co. and all newsdealers.



SPECIAL LOW RATES VIA THE NICKEL

to points in the West and Southwest. One way Colonist and round trip Homeseekers' rickets on asia first and colonist and round trip Homeseekers' rickets on asia first and local agentia, or write B. E. Fayner il inclusive. See Buffalo, N. Y., or A. W. Ecclestons, D. P. A., asi Broadway, New York.

FLOOR PROPOSITION

We will sell a limited number of treasury shares. de capitalisation, All common stock. No Bonda, Mortgages. Write for particulars. REGENERATED COLD AIR CO., 147 Milk Street



Export Trade

How to Secure and How to Hold It

Valuable hints on how to secure Export rade sent gratis on request. Address

EXPORT EXPERT
Box 773. New York

DRYING MACHINES, R. R. WORRELL.

Telegraphy & ctyles, 02 ap. OMNIGRAPH

WANTED—White Metal Articles to Cast. Alm Al kinds of Plating and Proce-work.

PRINTS YOUR NAME. SEE SHE 200

GE MACHINES Corline Engines, Browns and Bottlers Machinery, Tilk VII/TH MFG. CO., 800 Chinton St., Milweskee, Wa

LIGHT MACHINE CONSTRUCTION

National Supply Co., 835 Broadway, N.E.
Model Makes and Manufactures of
PATENTED ARTICLES, ETC.

MODELS & EXPERIMENTAL WORK inventions developed, Special Machiner E. V. BAILLARD, Fex Bidg., Franklin Square, New York

MODEL AND EXPERIMENTAL WORK EDWARD KLEINSCHMIDT, 82 W. Broadway, New York

AUTOMOBILE Parts. We are presented to man missions, carburetors, pumps, lithricators, ards. At complete spacifies care. Sheet metal at anning. Gase machine work. Good facilities. 30 years experience OTTO KONIGS-LOW. Cleveland, Ohlo.

DRAWING. Mechanical and Putent Office Drafting taught by mail. Write F. D. Lewis, 36 Liberty St., N. Y.

GOV'T AUCTION SALE CATALOG GUNS, BEGINL MACHINERY Tools and Disc. Modest Pistols, Military Goods (Illustrated), 18c., mailed &c. stamps. P. Banderman, Son Broadway, N. V. Castile Machine Works, & Centre St., Now York.

1903 EDITION

(NAVAL ENCYCLOPEDIA AND YEAR BOOK)
By FRED T. JANE, Author of the Naval Wear Garne (Kriegspiel),

Used as a text-book in European navies. The only absolutely correct and complete work of the kind published

414 PAGES. OBLONG QUARTO. CLOTH.

OVER 3,000 ILLUSTRATIONS. TH. PRICE, \$5.00, POST FREE.

PART I.—THE NAVIES OF THE WORLD: the Great Powers in Order of Strength; the Coast Defence Navies in Geographical Order.

PART II.—ARTICLES ON NAVAL PROGRESS DURING THE LAST TWELVE MONTHS. With a special article on Warship Engineering by Charles de Grave Fells, it inst C.E.,

PART III.—VIEWS AND OPINIONS ON NAVAL QUESTIONS. With a special article by Colonel V. U. Cuniberti, Chief Constructor of the Reyal Italian Navy.

PART IV.—SIGNALS AND SILHOUETTES (arranged in the same order as the Navies in Part I.).

CONTAINS :-A photograph of every warship in the world; also a slike gram of each vessel.

CONTAINS:-The length, beam, draught, horse power, speed. coal supply, number and at thickness and disposition of armor of every warship in the world.

CONTAINS: Tables of the size, weight, velocity, energy, penetration, etc., of every gun of every navy in the world.

CONTAINS :- A series of chapters by noted Admirals, Naval Constructors and other experts of various navies, on vital questions of the day in naval construction, tactics, and strategy.

CONTAINS :- A comparative table (by the author) of the strength of the navies of the world-the most accleratific attempt yet made to classify the world's warships and navies as to actual firsting strength.

IT SHOULD BE NOTED that this work is from the pen of a naval critic and expert, whose repulsation is far-teaching on both sides of the Atlantic. It will be not fascingling interest in the place in every library. of naval development, and as a book reference should

rticulars MUNN & CO., Publishers, 361 Broadway, New York.



THE WINTON SOTOR CARRI-GE CO., Cleveland, U.S.A.

Orient Buckboard



Model of No. With TWO NPEED. Price 8425.
WALTHAM MPG. CO., Waltham, Mass.

.m. Hass.

LAMBERT =

A "Wireless" Machine.

Multum in many Schinler, the late Proof.
Parvo. "Schiller in the late Proof.

Congress of the late Proof.

Co

DAPAULL OHBESLYAGE
CLAMPTALLS (bicage)
Lis La BI Clinical Mirrord.

nowflake—Aromatic—Pine nted Camphor Substitute

hemical amphor

Pure, White, Recrystallized. In One Pound Packages.

effective and economical estatistics of Campboor, Carbolic Acel and Taylo beganne flesh, Bli-drye and Inceles, Frevents and descripts Blips and Hot.

OFRECTIONS. - specialist LIBERALLY, or support that articles to be preparation, and wrong through the articles to be preparation, and wrong through the transfer of one articles and the support of the articles of the support of the articles of the support of the articles of the support of th 2 POUNDS BY MAIL, 30 CENTS

THEODORE METCALF CO.

New York, E. POUGERA & CO. longo, PETER VAN SCHAACK & SONS Prancisco, REDINGTON & COMPANY



The Leading Styles Originate in Brockton, the Manufact Center of Med's Fine Shoes in this Country. Styles Origin 8 by My Bruset Model Maker Are Conied Everythese

W. L. DOUGLAS Union \$3.50 SHOES, Worth Made, \$5.00,

red it is by-the only afference in the price. If I could take you into me horry at freechion, then, the largemen in the word tomed one root making men's lime above, and skew yor, the industs nave with which covery pair of Denglas those is made, you would realise why W. L. Denglas 18.00 shoes are the but them produced enzymber.

If I could also you the affine men not very Denglas 18.00 done or out make, which we have you the affine men of very Denglas 18.10 done now to make, why they fairly their pairs, it better, you be language, and and of greater internals value than any other \$1.50 sizes on the started be-day.

W. L. Douglas High-Grade Boys' Shoes, \$2.00 and \$1.75.

Douglas High-Grade Boys' Shoes, \$2.00 and \$1.75.

Coit is connected a very where its law they have been a second of the connected and produce the started better than the second of the connected and produce the second of the connected and produce the second of the connected and produce the second of the

produced. FAST COLOR ETHILITY USED EXCLESIVELY.

W. L. Doughas has the largest more 25.0 size Mail Order Rusiness in
the world. No trouble to get a fit by mail. State size and width; natrow,
medium or wide toe, with or without cap on toe; kind of leather deared;
congress, lace or button. Si centic extra propays delivery.

principal cities, and show dealers everywhere. No matter where you live,
Douglas shoes are within your reach. If you desire further information
tectors purchasing, write for fillustrated Catalogue.

W. L. DOUGLAS, 157 Spark Street, Breckton, Massach usetts.



Prices from \$2 000



For Hard-to-Shave Men

GEO. W. KORN RAZOR MPG. CO., DEPT. F LITTLE VALLEY, N.Y. Aprelia

CHARTER The APPLE GAB and GASOLINE
For All Work.
Stationaries, Portables, Honacers, Pumpers, Saving & Stoat Coulds,
Send for Catalogue and Testmonials.
State Your Power Needs.
CHARTER GAS ENGINE CO., Box 140, STERLING, ILL. Saves battery troubles, attached to any sia engine. Governors, Storage and Dry Batteries, Spark Coils, Plans, switches, Automatic Timing Devices. The Dayton Electrical Mile Co. Dynamo



Special Prices on

all the Best Tires
You'll save money by getting your
new tires from us. Write us what
you want and we'll quote you
prices that will prove it.

Scientific Disinfecting

Squabs Pay Boat Honse Mailer, need attention only part of time, bring big prices, Raised in one month. Attractive for posityrmen, farmers, women. Send for FRE, Bryth R. Hall German Hall Garn this immensity rich home-telestry.

Plymusth Bock Squab Co., 14 Friend St., Buston, Mass.

178 Milk St., Boston, Mano,



\$29.00

ABSOLUTELY SAFE

EASIER TO ROW

Mullins Galvanized

Made of seet. Practically indestructible. Air chamber each end. Cannot stak. Require no cashine. Ideal base for family use, summer parents.

Steel Pleasure Boats

W. H. MULLINS, 384 Depot St., SALEM, OHIO

SAVE ONE THIRD

poors toward get Davonstire St.,

By Buying of the Makers

by seiling direct to user and cutting out all dealers' profits.
All our goods carry our guarantee. Our free illustrated catalogue aboves a greater assortment of carriagus and barness than any desier can show you. Send for it.

THE COLUMBUS

CARRIAGE AND HARNESS COMPANY,
COLUMBUS, ORIO.





MORROW

Protect Your Life and the Lives of Others The only dependable coaster brake. Durable and safe always Specify R. Nat an experi-sent. Send for literature to-day. Thous-nds in me.

ECLIPSE MACHINE CO., Elmira, S. Y.

COLD GALVANIZING



NICKEL Hanson & Van Winki Kewark, N. J.
William St., N. Y.
William St., N. Y.
St. & 25 S. Canal St.
Chiongo.





The renaissance of bicycling brings with it one of the finest mechanical devices invented since the beginning of this industry.

THE TWO-SPEED GEAR CHAINLESS BICYCLE Readles the rider, by a slight pressure of foot on pedal, to change from high to low gear for hill climbing and difficult reads.

difficult roads.

Eastern Department, Hartford, Conn.

Columble" "Glovoland" "Tribune" "Crawford"

Western Department, Chicago, Ill.

"Crescent" "Ramble" "Bonarch" "Imperial"

Catalogues free at our 10,000 dealers' stores, or any one
Catalogue mailed on receipt of a two-sent stamp.

All varieties at lowest prices. Best Railros College and Also 1000 useful articles, including Safe Sering Machines, Bicycles, Tools, etc. Bar Railros, Christoper, Latta Press, Christoper, Christoper, Latta Press, Christop

Our Microscopes, Microtom Laboratory Glassware, Chemi Apparatus, Chemicala, Ph Leases and Shutters, Field Glass Projection Apparatus, Photo-Mi Lameras are used by the lead Laboratories and Government I partments Round the World, Catal Transport of the Catal

Bausch & Lomb Opt. Co.

U. S. A. LIQUID PISTOL

mes, etc. Retails for 89e. Good margin to the trade. ARKER, STEARNS & SUTTON, 226 South St., New York

NEW ENGLAND WATCHES The IOCKEY



The New England Watch Co NEW YORK OFFICE: LONDON OFFICE: 37 4 39 Maiden Lane 7 Snew Mill